



Republic of the Philippines
Province of Romblon
MUNICIPALITY OF SANTA FE

-OOO-

THE BIDS AND AWARDS COMMITTEE

SUPPLEMENTAL/BID BULLETIN NO. 01 S. 2023

CONSTRUCTION OF MUNICIPAL SLAUGHTERHOUSE

Date: February 7, 2023

This Supplemental/Bid Bulletin is issued to all prospective bidders to clarify or amend the Description of Work in Section VIII, Bill of Quantities of the Philippine Bidding Documents for the **Construction of Municipal Slaughterhouse**.

Original Provision:

Item No.	Description	Quantity	Unit	Unit Cost (Pesos)	Total Cost (Pesos)
SPL-1	Project Billboard, Occupational Safety and Health	1	lot		
SPL-2	TEMFACIL Contractor Field Office and Utilities	1	lot		
800	Clearing and Grubbing	1	lot		
803	Excavation Site Preparation, Excavation of Footing, Wall Footing, Tie Beam, Tank, perimeter fence & canal	1	lot		
804	Embankment/Backfilling, Gravel Bedding Backfilling and Compaction of Slab on Grade Concrete Steps & all the ground of site area, access road	1	lot		
404	Reinforcing Steel	1	lot		

	Fabrication & Installation of Reinforcing Bar, Structural Member & Perimeter Fence				
900	Concrete Works Formworks and Scaffolding	1	lot		
900	Concrete Works Placing of Concrete for Footing, Columns, Ramp Slab, FTB, WF, Roofbeam, SOG, Slab and Concrete Cover STP, Electrical Pedestal, Perimeter Fence & Canal	1	lot		
506	Masonry Works CHB Laying and Plastering for SLH Walls, Septic Tank, Waste Water Tank, Condemnation Pit and Canal and Perimeter Fence	1	lot		
1003	Metal Works Fabrication/Installation of trusses, Rafter and Railings, Purlins, Fascia Frame, Steel Grafting, Retraining Pen, Knocking Pen and Perimeter Fence & Gate 1 & 2	1	lot		
1014	Pre-Painted Metal Sheets	1	lot		
1006	Doors and Windows	1	lot		
1100/1102	Electrical Works	1	lot		
1032	Painting Works Interior/Exterior Wall of Slaughterhouse and Holding Pen	1	lot		
506	Carpentry Works Ceiling Frame Works, Board Installation, Facia Board Installation	1	lot		
1018	Tile Works Installation of tiles for CR (Wall and Floor), shower, Admin office and locker, offal cleaning lavatory	1	lot		
1600/1603	Plumbing Works	1	lot		
1718/1721	Sanitary Works Sewarage System	1	lot		
I	Equipments				

	<p>Delivery, Installation and Commissioning of Slaughter House Equipment</p> <p>1. Electric Hog Stunner - 220V AC input, 110/220V AC output 1 phase with enclosure. Includes power switch, safety switch pilot lamps, contactor and thermal fuses</p> <p>2. Scalding Vat - 6mm thick s/s t304 full welded construction w/50mm dia s/s drain gate valves, lifter & counter weight. Includes furnace construction w/fire bricks insulation & 250mm dia heat resistant chimney 1.5 meters extended from roof top. Includes s/s hook (130mm (L) & 10mm diameter) Dimension: 1800mm (L) x 1200mm(W) x 600mm(H)</p> <p>3. Hood Scalding Vat - 900mm diameter cast iron, includes furnace with SK32 firebrick insulation and 150mm dia chimney with SK32 fire brick insulation, chimney firebrick extended 1.50m high at the roof toop</p> <p>4. Dehairing Table - 36mm dia s/s tubular legs & frame w/ adjustable base jack, 32mm s/s pipe table top & tipping down chute at 150mm spacing o.c. full welded construction (SS304 Materials) Dimension: 1200mm(W) x 1800mm(L) x 600mm(H)</p> <p>5. Overhead Railing System - W/ section structure rail support type A35 steel, W/ s/s rod shifter, 12x63mm flat bar overhead meat rail hangers and rail track switchers. Primer coated, enamel finished</p> <p>6. Hog Trolley - 95mm dia roller w/ bushing & flat bar frame machine pressed w/ swivel axle & hot dip galvanize finished includes 12mm dia s/s t304 hook length: 600mm</p> <p>7. Hog Gambrel - Made of s/s t304 shafting 16mm gambrels & 8mm lifting lug Length: 530mm total length</p>	<p>1</p> <p>1</p> <p>1</p> <p>1</p> <p>20</p> <p>8</p> <p>8</p>	<p>Set</p> <p>Set</p> <p>Set</p> <p>Pc</p> <p>l.m.</p> <p>pcs</p> <p>pcs</p>		
--	--	---	--	--	--

	<p>8. Viscera Inspection Table - 1.5mm thick s/s t304 w/ 38mm drain, 25mm dia s/s t304 legs support w/ adjustable base jack and tilting ban, Dimension: 1000mm(L) x 600mm(W) x 800mm(H)</p> <p>9. Sticking Platform w/ Blood Trough - 1.5mm thk s/s t304 38mm dia. Tubular frame & 32mm table top, conveyerize, includes bleeding funnel, note: varies on floor area</p> <p>10. Overhead Weighing Scale - 300 kgs capacity, 200g grad, digital display indicator, 220Vac, 60Hz, 1 ph, includes printed 2 shear type load and steel weight section</p> <p>CATTLE LINE:</p> <p>11. MATADOR (PITTING KNIFE) 4</p> <p>12. CHAIN BLOCK 2 - 1 Ton capacity</p> <p>13. BEEF TROLLEY 4 - 120mm dia roller with bushing and flat bar frame machine pressed, swivel axle, assembly is hot dipped galvanized finish. Meat hooks are at least 16mm dia s/s t304. Length: 600mm</p> <p>AUXILIARY LINE:</p> <p>14. HANDWASHING FACILITY 3 - includes liquid soap dispenser foot operated and hand dryer all s/s t304 construction</p> <p>15. PLASTIC CURTAIN 2 - 3mm x 200mm industrial pvc plastic curtain anti-insect includes accessories & installation</p> <p>16. WORK PLATFORM 1 - Checkered plate s/s t304, 50mm dia pipe tubular leg & frame. Full welded construction. Dimension: 900mm(L) x 600mm(W) x 300mm(H)</p> <p>17. PAUNCH TRUCK 1 - 4.5mm thick s/s t304 tub construction w/ tubular handle w/ 2 fixed & 1 swivel caster wheels, includes viscera tilting pan</p> <p>17. 5 Steps working Platform, Checker Plate (SS304), 50mm 1</p>	<p>1</p> <p>1</p> <p>1</p> <p>4</p> <p>2</p> <p>4</p> <p>3</p> <p>2</p> <p>1</p> <p>1</p> <p>1</p>	<p>set</p> <p>pc</p> <p>pc</p> <p>pcs</p> <p>sets</p> <p>pcs</p> <p>sets</p> <p>rolls</p> <p>set</p> <p>pc</p> <p>lot</p>		
--	---	--	---	--	--

	Pipe Tubular Leg and Frame Fully Welded construction with buil-in Tool Dip and Hand Dip, 2.0m height with guard rails (SS304 Pipe) and caster wheel with lock	5	pcs		
	18. Hand Dip and Tool Dip with drain and valve (SS304 Materials)	9	l.m.		
	19. Offal Hanger - 10mm dia subs 304 hanger, for fixed hanger (5 hangers/lm) with stainless bracket	3	pcs		
	20.KAWA/TULYAS #50	1	set		
	21. Pressure Washer with 1 roll rubber hose				

Amendments:

Item No.	Description	Quantity	Unit	Unit Cost (Pesos)	Total Cost (Pesos)
SPL-1	Project Billboard, Occupational Safety and Health	1	lot		
SPL-2	TEMFACIL Contractor Field Office and Utilities	1	lot		
800	Clearing and Grubbing Site Clearing	1	lot		
803	Excavation Site Preparation, Excavation of Footing, Wall Footing, Tie Beam, Tank, perimeter fence & canal	1	lot		
804	Embankment/Backfilling, Gravel Bedding Backfilling and Compaction of Slab on Grade Concrete Steps & all the ground of site area, access road	1	lot		
404	Reinforcing Steel Fabrication & Installation of Reinforcing Bar, Structural Member & Perimeter Fence	1	lot		

900	Concrete Works Formworks and Scaffolding	1	lot		
900	Concrete Works Placing of Concrete for Footing, Columns, Ramp Slab, FTB, WF, Roofbeam, SOG, Slab and Concrete Cover STP, Electrical Pedestal, Perimeter Fence & Canal	1	lot		
506	Masonry Works CHB Laying and Plastering for SLH Walls, Septic Tank, Waste Water Tank, Condemnation Pit and Canal and Perimeter Fence	1	lot		
1003	Metal Works Fabrication/Installation of trusses, Rafter and Railings, Purlins, Fascia Frame, Steel Grafting, Retraining Pen, Knocking Pen and Perimeter Fence & Gate 1 & 2	1	lot		
1014	Pre-Painted Metal Sheets Installation of Roofing	1	lot		
1006	Doors and Windows Refer to the Plan	1	lot		
1100/1102	Electrical Works Power Panel Boards and Circuit Protection, Manual Transfer Switch (230V, 1 phase, 60 Hz), Main ECB (230V, 1 Phase, 60 Hz), Wires and Cables, Electrical Raceway Conduit and Boxes, Lighting Devices and Ceiling Mounted Devices, Wiring Devices and Switches, Back Up Power Generator, Transformer and Metering, Other Items to Complete the Work, CCTV	1	lot		
1032	Painting Works Interior/Exterior Wall of Slaughterhouse and Holding Pen	1	lot		

506	Carpentry Works Ceiling Frame Works, Board Installation, Facia Board Installation	1	lot		
1018	Tile Works Installation of tiles for CR (Wall and Floor), shower, Admin office and locker, offal cleaning lavatory	1	lot		
1600/1603	Plumbing Works Clean Water Line and Accessories	1	lot		
1718/1721	Sanitary Works Seawarage System	1	lot		
I	Equipments Delivery, Installation and Commissioning of Slaughter House Equipment 1. Electric Hog Stunner - 220V AC input, 110/220V AC output 1 phase with enclosure. Includes power switch, safety switch pilot lamps, contactor and thermal fuses 2. Scalding Vat - 6mm thick s/s t304 full welded construction w/50mm dia s/s drain gate valves, lifter & counter weight. Includes furnace construction w/fire bricks insulation & 250mm dia heat resistant chimney 1.5 meters extended from roof top. Includes s/s t304 solid rod (1000mm(L) & 16mm diameter hook (130mm (L) & 10mm diameter) Dimension: 1800mm (L) x 1200mm(W) x 600mm(H) 3. Hood Scalding Vat - 900mm diameter cast iron, includes furnace with SK32 firebrick insulation and 150mm dia chimney with SK32 fire brick insulation, chimney firebrick extended 1.50m high at the roof toop 4. Dehairing Table - 36mm dia s/s tubular legs & frame w/ adjustable base jack, 32mm s/s pipe table top & tipping down chute at 150mm spacing o.c.	1	Set		
		1	Set		
		1	Set		
		1	Pc		

	<p>full welded construction (SS304 Materials) Dimension: 1200mm(W) x 1800mm(L) x 600mm(H)</p> <p>5. Overhead Railing System - W/ section structure rail support type A36 steel, W/ s/s rod shifter, 12x63mm flat bar overhead meat rail & 10x63mm. Flat bar rail hangers and rail track switches. Primer coated, enamel finished</p> <p>6. Hog Trolley - 95mm dia roller w/ bushing & flat bar frame machine pressed w/ swivel axle & hot dip galvanize finished includes 12mm dia s/s t304 hook length: 600mm</p> <p>7. Hog Gambrel - Made of s/s t304 shafting 16mm gambrels & 8mm lifting lug Length: 530mm total length</p> <p>8. Viscera Inspection Table - 1.5mm thick s/s t304 w/ 38mm drain, 25mm dia s/s t304 legs support w/ adjustable base jack and tilting ban, Dimension: 1000mm(L) x 600mm(W) x 800mm(H)</p> <p>9. Sticking Platform w/ Blood Trough - 1.5mm thk s/s t304 38mm dia. Tubular frame & 32mm table top, conveyerize, includes bleeding funnel, note: varies on floor area</p> <p>10. Overhead Weighing Scale - 300 kgs capacity, 200g grad, digital display indicator, 220Vac, 60Hz, 1 ph, includes printed 2 shear type load and steel weight section</p> <p>CATTLE LINE:</p> <p>11. MATADOR (PITTING KNIFE)</p> <p>12. CHAIN BLOCK - 1 Ton capacity</p> <p>13. BEEF TROLLEY - 120mm dia roller with bushing and flat bar frame machine pressed, swivel axle, assembly is hot dipped galvanized finish. Meat hooks are at least 16mm dia s/s t304. Length: 600mm</p> <p>AUXILIARY LINE:</p> <p>14. HANDWASHING FACILITY</p>	<p>20</p> <p>8</p> <p>8</p> <p>1</p> <p>1</p> <p>1</p> <p>4</p> <p>2</p> <p>4</p> <p>3</p>	<p>l.m.</p> <p>pcs</p> <p>pcs</p> <p>set</p> <p>pc</p> <p>pc</p> <p>pcs</p> <p>sets</p> <p>pcs</p> <p>sets</p>		
--	--	--	--	--	--

	- includes liquid soap dispenser foot operated and hand dryer all s/s t304 construction			
	15. PLASTIC CURTAIN - 3mm x 200mm industrial pvc plastic curtain anti-insect includes accessories & installation	2	rolls	
	16. WORK PLATFORM - Checkered plate s/s t304, 50mm dia pipe tubular leg & frame. Fully welded construction. Dimension: 900mm(L) x 600mm(W) x 300mm(H)	1	set	
	17. PAUNCH TRUCK - 4.5mm thick s/s t304 tub construction w/ tubular handle w/ 2 fixed & 1 swivel caster wheels, includes viscera tilting pan	1	pc	
	18. 5 Steps working Platform, Checker Plate (SS304), 50mm Pipe Tubular Leg and Frame Fully Welded construction with built-in Tool Dip and Hand Dip, 2.0m height with guard rails (SS304 Pipe) and caster wheel with lock	1	lot	
	19. Hand Dip and Tool Dip with drain and valve (SS304 Materials)	5	pcs	
	20. Offal Hanger - 10mm dia subs 304 hanger, for fixed hanger (5 hangers/lm) with stainless bracket	9	l.m.	
	21. KAWA/TULYAS #50	3	pcs	
	22. Pressure Washer with 1 roll rubber hose	1	set	

This Supplemental/Bid Bulletin shall form an integral part of the Bidding Document.

For the guidance and information of all concerned.


CHARLIE T. ANDRES, JR.
 BAC Chairperson