

PHILIPPINE BIDDING DOCUMENTS



CONSTRUCTION OF SLAUGHTERHOUSE PHASE III

Government of the Republic of the Philippines

Date of Public Bidding: February 26, 2024

**Sixth Edition
July 2020**

Name of Procuring Entity

MUNICIPAL GOVERNMENT OF SANTA FE, ROMBLON

Standard Form Number: SF-INFR-08

Revised on: July 29, 2004

Checklist of Technical and Financial Documents

REVISED IMPLEMENTING RULE OF R.A. 9184

Contract: CONSTRUCTION OF SLAUGHTERHOUSE - PHASE III
Sitio Lungaog, Poblacion, Santa Fe, Romblon

Date: February 26, 2024

Bidder: _____

TECHNICAL COMPONENT ENVELOPE

Imp. Office	CHARLIET. ANDRES, JR. BAC Member	EMYLOW G. MACHON Member	DERRICK E. MAYOR Member	CARMEL P. PANAGSAGAN Vice-Chairperson	REYNALD T. SOLANOY BAC Chairperson
-------------	-------------------------------------	----------------------------	----------------------------	--	---------------------------------------

--	--	--	--	--	--

--	--	--	--	--	--

--	--	--	--	--	--

--	--	--	--	--	--

--	--	--	--	--	--

--	--	--	--	--	--

--	--	--	--	--	--

--	--	--	--	--	--

A) Class "A" Documents

1 Legal Documents

- 1.1 Valid PhilGEPS Registration Certificate (Platinum Membership) (all pages) in accordance with Section 8.5.2 of the IRR;

If Annex A is not updated in the PhilGEPS Platinum Certificate of Registration, the following shall be submitted:
 - 1.1.1 Registration Certificate from SEC, DTI for sole proprietorship, CDA for cooperatives,
 - 1.1.2 Mayor's Permit issued by the city or municipality where the principal place of business of the prospective bidder is located.
 - 1.1.3 Tax Clearance per E.O 398, s. 2005, as finally reviewed and approved by the Bureau of Internal Revenue (BIR).
 - 1.1.4 A valid Philippine Contractor's Accreditation Board (PCAB) License or Special PCAB License in case of Joint Ventures, and registration for the type and cost of contract to be Bid.
 - 1.1.5 The Prospective bidder's Audited Financial Statement, showing, among others, the prospective bidder's total and current assets and liabilities, stamped "received" by the BIR or its duly accredited and authorized institutions, for the preceding calendar year which should not be earlier than 2 years from the date of bid submission.

2 Technical Documents

- 2.1 Statement of the prospective bidder of all its ongoing government and private contracts, including contracts awarded but not yet started, if any, whether similar or not similar in nature and complexity to the contract to be bid
- 2.2 Statement of the bidder's Single Largest Completed Contract (SLCC) similar to the contract to be bid, and shall be supported by the following documents:
 - a. Notice of Award and/or Notice to Proceed
 - b. Contract Agreement
 - c. Constructors Performance Evaluation System (CPES) rating sheets, and/or Certificate of Final Acceptance issued by the owner
- 2.3 Special PCAB License in case of Joint Ventures and registration for the type and cost of the contract to be bid

Note: Any missing document in the above-mentioned checklist is a ground for outright of the bid.

Remarks: () Pass () Fail

Name of Procuring Entity

MUNICIPAL GOVERNMENT OF SANTA FE, ROMBLON

Standard Form Number: SF-INFR-35

Revised on: July 29, 2004

Checklist of Technical and Financial Documents

REVISED IMPLEMENTING RULE OF R.A. 9184

Contract: CONSTRUCTION OF SLAUGHTERHOUSE - PHASE III
Sitio Lungaog, Poblacion, Santa Fe, Romblon

Date: February 26, 2024

Bidder: _____

TECHNICAL COMPONENT ENVELOPE

Imp. Office	CHARLIET. ANDRES, JR. BAC Member	EWYLOW G. MACHON Member	DERRICK E. MAYOR Member	CARMEL P. PANAGSAGAN Vice-Chairperson	REYNALD T. SOLANOY BAC Chairperson
-------------	-------------------------------------	----------------------------	----------------------------	--	---------------------------------------

--	--	--	--	--	--

--	--	--	--	--	--

--	--	--	--	--	--

--	--	--	--	--	--

--	--	--	--	--	--

--	--	--	--	--	--

2 Technical Documents

- 2.4 Original copy of Bid Security. If in the form of a Surety Bond, submit also a certification issued by the Insurance Commission or original copy of Notarized Bid Securing Declaration Project Requirements, which shall include the following:
- 2.5 Duly Signed Organizational Chart for the contract to be bid.
- 2.6 Duly Signed List of Contractor's Key Personnel (viz, Project Manager, Project Engineers, Material's Engineers, Safety Officer and Foremen) to be assigned to the contract to be bid, with their complete qualification and experience data.
- 2.6 Duly Signed List of Contractor's Equipment units, which are owned, leased, and/or under purchase agreements, supported by proof of ownership, certification of availability of equipment from the equipment lessor/vendor for the duration of the project.
- 2.7 Original duly signed Omnibus Sworn Statement (OSS) and if applicable, Original Notarized Secretary's Certificate in case of a corporation, partnership, or cooperative; or Original Special Power of Attorney of all members of the joint venture giving full power and authority to its officer to sign the OSS and do acts to represent the Bidder.

3 Financial Documents

- 3.1 The prospective bidder's computation of Net Financial Contracting Capacity (NFCC)

B) Class "B" Documents

- 3.2 If applicable, duly signed joint venture agreement (JVA) in accordance with RA No. 4566 and its IRR in case the joint venture is already in existence or duly notarized statements from all the potential joint venture partners stating that they will enter into and abide by the provisions of the JVA in the instance that the bid is successful.

Note: Any missing document in the above-mentioned checklist is a ground for outright rejection of the bid.

Remarks: () Pass () Fail

Name of Procuring Entity

MUNICIPAL GOVERNMENT OF SANTA FE, ROMBLON

Standard Form Number: SF-INFRA-54

Revised on: August 11, 2004

CHECKLIST FOR FINANCIAL ENVELOPE REQUIREMENTS FOR THE BAC

Contract: CONSTRUCTION OF SLAUGHTERHOUSE - PHASE III
Sitio Lungaog, Poblacion, Santa Fe, Romblon

Bidder: _____

Date: February 26, 2024

Checklist of Bid Requirements

Shall contain the following information/documents and shall be opened only if the bidder has complied with the requirements in the Technical Envelope.

FINANCIAL COMPONENT ENVELOPE

Imp. Office	CHARLIET. ANDRES, JR. BAC Member	EMYLOW G. MACHON Member	DERRICK E. MAYOR Member	CARMEL P. PANAGSAGAN Vice-Chairperson	REYNALD T. SOLANOY BAC Chairperson

- 1 Original of duly signed and accomplished Financial Bid Form
- 2 Original of duly signed Bid Prices in the Bill of Quantities
- 3 Duly accomplished Detailed Estimates Form, including a summary sheet indicating the unit prices of construction materials, labor rates, and equipment rentals used in coming up with the Bid
- 4 Cash Flow by Quarter

Note: Any missing document in the above-mentioned checklist is a ground for outright rejection of the bid.

Remarks: () Pass () Fail

Name of Procuring Entity

MUNICIPAL GOVERNMENT OF SANTA FE, ROMBLON

Standard Form Number: SF-INFRA-54

Revised on: August 11, 2004

CHECKLIST FOR ADDITIONAL REQUIREMENTS FOR THE BAC

Contract: CONSTRUCTION OF SLAUGHTERHOUSE - PHASE III
Sitio Lungaog, Poblacion, Santa Fe, Romblon

Date: February 26, 2024

Bidder: _____

ADDITIONAL REQUIREMENTS

Imp. Office	CHARLIET. ANDRES, JR. BAC Member	EMYLOW G. MACHON Member	DERRICK E. MAYOR Member	CARMEL P. PANAGSAGAN Vice-Chairperson	REYNALD T. SOLANOY BAC Chairperson
-------------	-------------------------------------	----------------------------	----------------------------	--	---------------------------------------

POST-QUALIFICATIONS: LCB (lowest calculated bidder) to submit the ff. documents:

- 1 Latest Income Tax and Business Tax Returns filed through EFPS
- 2 BIR Certificate of Registration

Remarks: () Complying () Non-Complying

CHECKLIST FOR ADDITIONAL REQUIREMENTS FOR THE BAC

Contract: CONSTRUCTION OF SLAUGHTERHOUSE - PHASE III
Sitio Lungaog, Poblacion, Santa Fe, Romblon

Bidder: _____

Date: February 26, 2024

Imp. Office	CHARLIET. ANDRES, JR. BAC Member	EMYLOW G. MACHON Member	DERRICK E. MAYOR Member	CARMEL P. PANAGSAGAN Vice-Chairperson	REYNALD T. SOLANOY BAC Chairperson
-------------	-------------------------------------	----------------------------	----------------------------	--	---------------------------------------

ADDITIONAL PROJECT REQUIREMENTS

- 1 Duly signed authority of the signing official
- 2 Duly signed construction schedule and S-curve
- 3 Duly signed manpower schedule
- 4 Duly signed construction method
- 5 Duly signed equipment utilization schedule
- 6 Duly signed affidavit of site inspection
- 7 Duly signed Construction Safety and Health Program of the contractor approved by the Department of Labor and Employment (DOLE)
- 8 Duly signed PERT/CPM

Remarks: () Complying () Non-Complying

Preface

These Philippine Bidding Documents (PBDs) for the procurement of Infrastructure Projects (hereinafter referred to also as the “Works”) through Competitive Bidding have been prepared by the Government of the Philippines for use by all branches, agencies, departments, bureaus, offices, or instrumentalities of the government, including government-owned and/or -controlled corporations, government financial institutions, state universities and colleges, local government units, and autonomous regional government. The procedures and practices presented in this document have been developed through broad experience, and are for mandatory use in projects that are financed in whole or in part by the Government of the Philippines or any foreign government/foreign or international financing institution in accordance with the provisions of the 2016 revised Implementing Rules and Regulations (IRR) of Republic Act (RA) No. 9184.

The PBDs are intended as a model for admeasurements (unit prices or unit rates in a bill of quantities) types of contract, which are the most common in Works contracting.

The Bidding Documents shall clearly and adequately define, among others: (i) the objectives, scope, and expected outputs and/or results of the proposed contract; (ii) the eligibility requirements of Bidders; (iii) the expected contract duration; and (iv) the obligations, duties, and/or functions of the winning Bidder.

Care should be taken to check the relevance of the provisions of the PBDs against the requirements of the specific Works to be procured. If duplication of a subject is inevitable in other sections of the document prepared by the Procuring Entity, care must be exercised to avoid contradictions between clauses dealing with the same matter.

Moreover, each section is prepared with notes intended only as information for the Procuring Entity or the person drafting the Bidding Documents. They shall not be included in the final documents. The following general directions should be observed when using the documents:

- a. All the documents listed in the Table of Contents are normally required for the procurement of Infrastructure Projects. However, they should be adapted as necessary to the circumstances of the particular Project.
- b. Specific details, such as the “*name of the Procuring Entity*” and “*address for bid submission*,” should be furnished in the Instructions to Bidders, Bid Data Sheet, and Special Conditions of Contract. The final documents should contain neither blank spaces nor options.
- c. This Preface and the footnotes or notes in italics included in the Invitation to Bid, BDS, General Conditions of Contract, Special Conditions of Contract, Specifications, Drawings, and Bill of Quantities are not part of the text of the final document, although they contain instructions that the Procuring Entity should strictly follow.
- d. The cover should be modified as required to identify the Bidding Documents as to the names of the Project, Contract, and Procuring Entity, in addition to date of issue.

- e. Modifications for specific Procurement Project details should be provided in the Special Conditions of Contract as amendments to the Conditions of Contract. For easy completion, whenever reference has to be made to specific clauses in the Bid Data Sheet or Special Conditions of Contract, these terms shall be printed in bold typeface on Sections I (Instructions to Bidders) and III (General Conditions of Contract), respectively.
- f. For guidelines on the use of Bidding Forms and the procurement of Foreign-Assisted Projects, these will be covered by a separate issuance of the Government Procurement Policy Board.

TABLE OF CONTENTS

Glossary of Terms, Abbreviations, and Acronyms	5
Section I. Invitation to Bid	8
Section II. Instructions to Bidders	11
1. Scope of Bid	12
2. Funding Information	12
3. Bidding Requirements.....	12
4. Corrupt, Fraudulent, Collusive, Coercive, and Obstructive Practices	12
5. Eligible Bidders.....	12
6. Origin of Associated Goods	13
7. Subcontracts	13
8. Pre-Bid Conference	14
9. Clarification and Amendment of Bidding Documents.....	14
10. Documents Comprising the Bid: Eligibility and Technical Components	14
11. Documents Comprising the Bid: Financial Component	15
12. Alternative Bids.....	15
13. Bid Prices	15
14. Bid and Payment Currencies	15
15. Bid Security.....	15
16. Sealing and Marking of Bids.....	16
17. Deadline for Submission of Bids	16
18. Opening and Preliminary Examination of Bids	16
19. Detailed Evaluation and Comparison of Bids	16
20. Post Qualification.....	17
21. Signing of the Contract	17
Section III. Bid Data Sheet.....	18
Section IV. General Conditions of Contract	21
1. Scope of Contract	22
2. Sectional Completion of Works	22
3. Possession of Site	22
4. The Contractor's Obligations.....	22
5. Performance Security	23
6. Site Investigation Reports	23

7.	Warranty	23
8.	Liability of the Contractor	23
9.	Termination for Other Causes	23
10.	Dayworks	24
11.	Program of Work.....	24
12.	Instructions, Inspections and Audits	24
13.	Advance Payment.....	24
14.	Progress Payments.....	24
15.	Operating and Maintenance Manuals.....	24
Section V. Special Conditions of Contract		26
Section VI. Specifications.....		28
Section VII. Drawings		30
Section VIII. Bill of Quantities		31
Section IX. Checklist of Technical and Financial Documents.....		34

Glossary of Terms, Abbreviations, and Acronyms

ABC – Approved Budget for the Contract.

ARCC – Allowable Range of Contract Cost.

BAC – Bids and Awards Committee.

Bid – A signed offer or proposal to undertake a contract submitted by a bidder in response to and in consonance with the requirements of the bidding documents. Also referred to as *Proposal* and *Tender*. (2016 revised IRR, Section 5[c])

Bidder – Refers to a contractor, manufacturer, supplier, distributor and/or consultant who submits a bid in response to the requirements of the Bidding Documents. (2016 revised IRR, Section 5[d])

Bidding Documents – The documents issued by the Procuring Entity as the bases for bids, furnishing all information necessary for a prospective bidder to prepare a bid for the Goods, Infrastructure Projects, and/or Consulting Services required by the Procuring Entity. (2016 revised IRR, Section 5[e])

BIR – Bureau of Internal Revenue.

BSP – Bangko Sentral ng Pilipinas.

CDA – Cooperative Development Authority.

Consulting Services – Refer to services for Infrastructure Projects and other types of projects or activities of the GOP requiring adequate external technical and professional expertise that are beyond the capability and/or capacity of the GOP to undertake such as, but not limited to: (i) advisory and review services; (ii) pre-investment or feasibility studies; (iii) design; (iv) construction supervision; (v) management and related services; and (vi) other technical services or special studies. (2016 revised IRR, Section 5[i])

Contract – Refers to the agreement entered into between the Procuring Entity and the Supplier or Manufacturer or Distributor or Service Provider for procurement of Goods and Services; Contractor for Procurement of Infrastructure Projects; or Consultant or Consulting Firm for Procurement of Consulting Services; as the case may be, as recorded in the Contract Form signed by the parties, including all attachments and appendices thereto and all documents incorporated by reference therein.

Contractor – is a natural or juridical entity whose proposal was accepted by the Procuring Entity and to whom the Contract to execute the Work was awarded. Contractor as used in these Bidding Documents may likewise refer to a supplier, distributor, manufacturer, or consultant.

CPI – Consumer Price Index.

DOLE – Department of Labor and Employment.

DTI – Department of Trade and Industry.

Foreign-funded Procurement or Foreign-Assisted Project – Refers to procurement whose funding source is from a foreign government, foreign or international financing institution as specified in the Treaty or International or Executive Agreement. (2016 revised IRR, Section 5[b]).

GFI – Government Financial Institution.

GOCC – Government-owned and/or –controlled corporation.

Goods – Refer to all items, supplies, materials and general support services, except Consulting Services and Infrastructure Projects, which may be needed in the transaction of public businesses or in the pursuit of any government undertaking, project or activity, whether in the nature of equipment, furniture, stationery, materials for construction, or personal property of any kind, including non-personal or contractual services such as the repair and maintenance of equipment and furniture, as well as trucking, hauling, janitorial, security, and related or analogous services, as well as procurement of materials and supplies provided by the Procuring Entity for such services. The term “related” or “analogous services” shall include, but is not limited to, lease or purchase of office space, media advertisements, health maintenance services, and other services essential to the operation of the Procuring Entity. (2016 revised IRR, Section 5[r])

GOP – Government of the Philippines.

Infrastructure Projects – Include the construction, improvement, rehabilitation, demolition, repair, restoration or maintenance of roads and bridges, railways, airports, seaports, communication facilities, civil works components of information technology projects, irrigation, flood control and drainage, water supply, sanitation, sewerage and solid waste management systems, shore protection, energy/power and electrification facilities, national buildings, school buildings, hospital buildings, and other related construction projects of the government. Also referred to as *civil works or works*. (2016 revised IRR, Section 5[u])

LGUs – Local Government Units.

NFCC – Net Financial Contracting Capacity.

NGA – National Government Agency.

PCAB – Philippine Contractors Accreditation Board.

PhilGEPS - Philippine Government Electronic Procurement System.

Procurement Project – refers to a specific or identified procurement covering goods, infrastructure project or consulting services. A Procurement Project shall be described, detailed, and scheduled in the Project Procurement Management Plan prepared by the agency which shall be consolidated in the procuring entity's Annual Procurement Plan. (GPPB Circular No. 06-2019 dated 17 July 2019)

PSA – Philippine Statistics Authority.

SEC – Securities and Exchange Commission.

SLCC – Single Largest Completed Contract.

UN – United Nations.

Section I. Invitation to Bid

Notes on the Invitation to Bid

The Invitation to Bid (IB) provides information that enables potential Bidders to decide whether to participate in the procurement at hand. The IB shall be posted in accordance with Section 21.2 of the 2016 revised IRR of RA No. 9184.

Apart from the essential items listed in the Bidding Documents, the IB should also indicate the following:

- a. The date of availability of the Bidding Documents, which shall be from the time the IB is first advertised/posted until the deadline for the submission and receipt of bids;
- b. The place where the Bidding Documents may be acquired or the website where it may be downloaded;
- c. The deadline for the submission and receipt of bids; and
- d. Any important bid evaluation criteria.

The IB should be incorporated into the Bidding Documents. The information contained in the IB must conform to the Bidding Documents and in particular to the relevant information in the Bid Data Sheet.



Republic of the Philippines
Province of Romblon
MUNICIPALITY OF SANTA FE
-o0o-

THE BIDS AND AWARDS COMMITTEE

**Invitation to Bid for the
CONSTRUCTION OF SLAUGHTERHOUSE – PHASE III**

1. The *Municipal Government of Santa Fe, Romblon*, through the *20% Development Fund 2022* intends to apply the sum of *One Million Four Hundred Ninety Nine Thousand & 82/100 (P1,499,999.82)* being the Approved Budget for the Contract (ABC) to payments under the contract for *Construction of Slaughterhouse – Phase III (ITB No. 2024-0013)*. Bids received in excess of the ABC shall be automatically rejected at bid opening.
2. The *Municipal Government of Santa Fe, Romblon* now invites bids for the above Procurement Project. Completion of the Works is required within *35 Calendar Days*. Bidders should have completed a contract similar to the Project. The description of an eligible bidder is contained in the Bidding Documents, particularly, in Section II (Instructions to Bidders).
3. Bidding will be conducted through open competitive bidding procedures using non-discretionary “*pass/fail*” criterion as specified in the 2016 revised Implementing Rules and Regulations (IRR) of Republic Act (RA) No. 9184.
4. Interested bidders may obtain further information from the *Municipal Government of Santa Fe, Romblon* and inspect the Bidding Documents at the address given below during working days from *8:00 A.M. to 5:00 P.M.*
5. A complete set of Bidding Documents may be acquired by interested bidders on *February 5, 2024 to February 26, 2024* from given address and website/s below and upon payment of the applicable fee for the Bidding Documents, pursuant to the latest Guidelines issued by the GPPB, in the amount of *Five Thousand Pesos (P 5,000.00)*. The Procuring Entity shall allow the bidder to present its proof of payment for the fees to be presented in person or through electronic means.
6. The *Municipal Government of Santa Fe, Romblon* will hold a Pre-Bid Conference¹ on *February 12, 2024 at 1:30 in the afternoon* at the *Municipal Hall, Poblacion, Santa Fe, Romblon*, which shall be open to prospective bidders.
7. Bids must be duly received by the BAC Secretariat through manual submission at the office address as indicated below on or before *February 26, 2024 at 9:00 o'clock in the morning*. Late bids shall not be accepted.

¹ May be deleted in case the ABC is less than One Million Pesos (PhP1,000,000) where the Procuring Entity may not hold a pre-bid conference.

8. All bids must be accompanied by a bid security in any of the acceptable forms and in the amount stated in **ITB** Clause 16.
9. Bid opening shall be on *February 26, 2024 at 9:00 o'clock in the morning* at the given address below. Bids will be opened in the presence of the bidders' representatives who choose to attend the activity.
10. The *Municipal Government of Santa Fe, Romblon* reserves the right to reject any and all bids, declare a failure of bidding, or not award the contract at any time prior to contract award in accordance with Sections 35.6 and 41 of the 2016 revised Implementing Rules and Regulations (IRR) of RA No. 9184, without thereby incurring any liability to the affected bidder or bidders.
11. For further information, please refer to:

ENGR. REYNALD T. SOLANOY

Municipal Assessor

Municipality of Santa Fe

Province of Romblon

Telephone No. 0917-154-2647

Email Address: stafebac2023@gmail.com

12. You may visit our website:

For downloading of Bidding Documents: <http://www.staferomblon.gov.ph>



REYNALD T. SOLANOY
BAC Chairperson

Section II. Instructions to Bidders

Notes on the Instructions to Bidders

This Section on the Instruction to Bidders (ITB) provides the information necessary for bidders to prepare responsive bids, in accordance with the requirements of the Procuring Entity. It also provides information on bid submission, eligibility check, opening and evaluation of bids, post-qualification, and on the award of contract.

1. Scope of Bid

The Procuring Entity, *Municipal Government of Santa Fe, Romblon* invites Bids for the *Construction of Slaughterhouse – Phase III*, with Project Identification Number *ITB No. 2024-0013*.

The Procurement Project (referred to herein as “Project”) is for the construction of Works, as described in Section VI (Specifications).

2. Funding Information

2.1. The GOP through the source of funding as indicated below for *20% Development Fund 2022* in the amount of *One Million Four Hundred Ninety Nine Thousand Nine Hundred Ninety Nine Pesos & 82/100 (P 1,499,999.82)*.

2.2. The source of funding is:

LGUs, the Annual or Supplemental Budget, as approved by the Sanggunian.

3. Bidding Requirements

The Bidding for the Project shall be governed by all the provisions of RA No. 9184 and its 2016 revised IRR, including its Generic Procurement Manual and associated policies, rules and regulations as the primary source thereof, while the herein clauses shall serve as the secondary source thereof.

Any amendments made to the IRR and other GPPB issuances shall be applicable only to the ongoing posting, advertisement, or invitation to bid by the BAC through the issuance of a supplemental or bid bulletin.

The Bidder, by the act of submitting its Bid, shall be deemed to have inspected the site, determined the general characteristics of the contracted Works and the conditions for this Project, such as the location and the nature of the work; (b) climatic conditions; (c) transportation facilities; (c) nature and condition of the terrain, geological conditions at the site communication facilities, requirements, location and availability of construction aggregates and other materials, labor, water, electric power and access roads; and (d) other factors that may affect the cost, duration and execution or implementation of the contract, project, or work and examine all instructions, forms, terms, and project requirements in the Bidding Documents.

4. Corrupt, Fraudulent, Collusive, Coercive, and Obstructive Practices

The Procuring Entity, as well as the Bidders and Contractors, shall observe the highest standard of ethics during the procurement and execution of the contract. They or through an agent shall not engage in corrupt, fraudulent, collusive, coercive, and obstructive practices defined under Annex “I” of the 2016 revised IRR of RA No. 9184 or other integrity violations in competing for the Project.

5. Eligible Bidders

- 5.1. Only Bids of Bidders found to be legally, technically, and financially capable will be evaluated.
- 5.2. The Bidder must have an experience of having completed a Single Largest Completed Contract (SLCC) that is similar to this Project, equivalent to at least fifty percent (50%) of the ABC adjusted, if necessary, by the Bidder to current prices using the PSA's CPI, except under conditions provided for in Section 23.4.2.4 of the 2016 revised IRR of RA No. 9184.

A contract is considered to be "similar" to the contract to be bid if it has the major categories of work stated in the **BDS**.
- 5.3. For Foreign-funded Procurement, the Procuring Entity and the foreign government/foreign or international financing institution may agree on another track record requirement, as specified in the Bidding Document prepared for this purpose.
- 5.4. The Bidders shall comply with the eligibility criteria under Section 23.4.2 of the 2016 IRR of RA No. 9184.

6. **Origin of Associated Goods**

There is no restriction on the origin of Goods other than those prohibited by a decision of the UN Security Council taken under Chapter VII of the Charter of the UN.

7. **Subcontracts**

- 7.1. The Bidder may subcontract portions of the Project to the extent allowed by the Procuring Entity as stated herein, but in no case more than fifty percent (50%) of the Project.

The Procuring Entity has prescribed that:

- a. Subcontracting is not allowed.

- 7.1. *[If Procuring Entity has determined that subcontracting is allowed during the bidding , state:]* The Bidder must submit together with its Bid the documentary requirements of the subcontractor(s) complying with the eligibility criterial stated in **ITB** Clause 5 in accordance with Section 23.4 of the 2016 revised IRR of RA No. 9184 pursuant to Section 23.1 thereof.

- 7.2. *[If subcontracting is allowed during the contract implementation stage, state:]* The Supplier may identify its subcontractor during the contract implementation stage. Subcontractors identified during the bidding may be changed during the implementation of this Contract. Subcontractors must submit the documentary requirements under Section 23.1 of the 2016 revised IRR of RA No. 9184 and comply with the eligibility criteria specified in **ITB** Clause 5 to the implementing or end-user unit.

- 7.3. Subcontracting of any portion of the Project does not relieve the Contractor of any liability or obligation under the Contract. The Supplier will be responsible for the acts, defaults, and negligence of any subcontractor, its agents, servants, or workmen as fully as if these were the Contractor's own acts, defaults, or negligence, or those of its agents, servants, or workmen.

8. Pre-Bid Conference

The Procuring Entity will hold a pre-bid conference for this Project on the specified date and time and either at its physical address as indicated in paragraph 6 of the **IB**.

9. Clarification and Amendment of Bidding Documents

Prospective bidders may request for clarification on and/or interpretation of any part of the Bidding Documents. Such requests must be in writing and received by the Procuring Entity, either at its given address or through electronic mail indicated in the **IB**, at least ten (10) calendar days before the deadline set for the submission and receipt of Bids.

10. Documents Comprising the Bid: Eligibility and Technical Components

- 10.1. The first envelope shall contain the eligibility and technical documents of the Bid as specified in **Section IX. Checklist of Technical and Financial Documents**.
- 10.2. If the eligibility requirements or statements, the bids, and all other documents for submission to the BAC are in foreign language other than English, it must be accompanied by a translation in English, which shall be authenticated by the appropriate Philippine foreign service establishment, post, or the equivalent office having jurisdiction over the foreign bidder's affairs in the Philippines. For Contracting Parties to the Apostille Convention, only the translated documents shall be authenticated through an apostille pursuant to GPPB Resolution No. 13-2019 dated 23 May 2019. The English translation shall govern, for purposes of interpretation of the bid.
- 10.3. A valid special PCAB License in case of Joint Ventures, and registration for the type and cost of the contract for this Project. Any additional type of Contractor license or permit shall be indicated in the **BDS**.
- 10.4. A List of Contractor's key personnel (e.g., Project Manager, Project Engineers, Materials Engineers, and Foremen) assigned to the contract to be bid, with their complete qualification and experience data shall be provided. These key personnel must meet the required minimum years of experience set in the **BDS**.
- 10.5. A List of Contractor's major equipment units, which are owned, leased, and/or under purchase agreements, supported by proof of ownership, certification of availability of equipment from the equipment lessor/vendor for the duration of

the project, as the case may be, must meet the minimum requirements for the contract set in the **BDS**.

11. Documents Comprising the Bid: Financial Component

- 11.1. The second bid envelope shall contain the financial documents for the Bid as specified in **Section IX. Checklist of Technical and Financial Documents**.
- 11.2. Any bid exceeding the ABC indicated in paragraph 1 of the **IB** shall not be accepted.
- 11.3. For Foreign-funded procurement, a ceiling may be applied to bid prices provided the conditions are met under Section 31.2 of the 2016 revised IRR of RA No. 9184.

12. Alternative Bids

Bidders shall submit offers that comply with the requirements of the Bidding Documents, including the basic technical design as indicated in the drawings and specifications. Unless there is a value engineering clause in the **BDS**, alternative Bids shall not be accepted.

13. Bid Prices

All bid prices for the given scope of work in the Project as awarded shall be considered as fixed prices, and therefore not subject to price escalation during contract implementation, except under extraordinary circumstances as determined by the NEDA and approved by the GPPB pursuant to the revised Guidelines for Contract Price Escalation guidelines.

14. Bid and Payment Currencies

- 14.1. Bid prices may be quoted in the local currency or tradeable currency accepted by the BSP at the discretion of the Bidder. However, for purposes of bid evaluation, Bids denominated in foreign currencies shall be converted to Philippine currency based on the exchange rate as published in the BSP reference rate bulletin on the day of the bid opening.

14.2. *Payment of the contract price shall be made in:*

- a. Philippine Pesos.

15. Bid Security

- 15.1. The Bidder shall submit a Bid Securing Declaration or any form of Bid Security in the amount indicated in the **BDS**, which shall be not less than the percentage of the ABC in accordance with the schedule in the **BDS**.

- 15.2. The Bid and bid security shall be valid until *[indicate date]*. Any bid not accompanied by an acceptable bid security shall be rejected by the Procuring Entity as non-responsive.

16. Sealing and Marking of Bids

Each Bidder shall submit one copy of the first and second components of its Bid.

The Procuring Entity may request additional hard copies and/or electronic copies of the Bid. However, failure of the Bidders to comply with the said request shall not be a ground for disqualification.

If the Procuring Entity allows the submission of bids through online submission to the given website or any other electronic means, the Bidder shall submit an electronic copy of its Bid, which must be digitally signed. An electronic copy that cannot be opened or is corrupted shall be considered non-responsive and, thus, automatically disqualified.

17. Deadline for Submission of Bids

The Bidders shall submit on the specified date and time and either at its physical address or through online submission as indicated in paragraph 7 of the **IB**.

18. Opening and Preliminary Examination of Bids

- 18.1. The BAC shall open the Bids in public at the time, on the date, and at the place specified in paragraph 9 of the **IB**. The Bidders' representatives who are present shall sign a register evidencing their attendance. In case videoconferencing, webcasting or other similar technologies will be used, attendance of participants shall likewise be recorded by the BAC Secretariat.

In case the Bids cannot be opened as scheduled due to justifiable reasons, the rescheduling requirements under Section 29 of the 2016 revised IRR of RA No. 9184 shall prevail.

- 18.2. The preliminary examination of Bids shall be governed by Section 30 of the 2016 revised IRR of RA No. 9184.

19. Detailed Evaluation and Comparison of Bids

- 19.1. The Procuring Entity's BAC shall immediately conduct a detailed evaluation of all Bids rated "*passed*" using non-discretionary pass/fail criteria. The BAC shall consider the conditions in the evaluation of Bids under Section 32.2 of 2016 revised IRR of RA No. 9184.

- 19.2. If the Project allows partial bids, all Bids and combinations of Bids as indicated in the **BDS** shall be received by the same deadline and opened and evaluated simultaneously so as to determine the Bid or combination of Bids offering the lowest calculated cost to the Procuring Entity. Bid Security as

required by **ITB** Clause 15 shall be submitted for each contract (lot) separately.

- 19.3. In all cases, the NFCC computation pursuant to Section 23.4.2.6 of the 2016 revised IRR of RA No. 9184 must be sufficient for the total of the ABCs for all the lots participated in by the prospective Bidder.

20. Post Qualification

Within a non-extendible period of five (5) calendar days from receipt by the Bidder of the notice from the BAC that it submitted the Lowest Calculated Bid, the Bidder shall submit its latest income and business tax returns filed and paid through the BIR Electronic Filing and Payment System (eFPS), and other appropriate licenses and permits required by law and stated in the **BDS**.

21. Signing of the Contract

The documents required in Section 37.2 of the 2016 revised IRR of RA No. 9184 shall form part of the Contract. Additional Contract documents are indicated in the **BDS**.

Section III. Bid Data Sheet

Notes on the Bid Data Sheet (BDS)

The Bid Data Sheet (BDS) consists of provisions that supplement, amend, or specify in detail, information, or requirements included in the ITB found in Section II, which are specific to each procurement.

This Section is intended to assist the Procuring Entity in providing the specific information in relation to corresponding clauses in the ITB and has to be prepared for each specific procurement.

The Procuring Entity should specify in the BDS information and requirements specific to the circumstances of the Procuring Entity, the processing of the procurement, and the bid evaluation criteria that will apply to the Bids. In preparing the BDS, the following aspects should be checked:

- a. Information that specifies and complements provisions of the ITB must be incorporated.
- b. Amendments and/or supplements, if any, to provisions of the ITB as necessitated by the circumstances of the specific procurement, must also be incorporated.

Bid Data Sheet

ITB Clause																						
5.2	For this purpose, contracts similar to the Project refer to contracts which have the same major categories of work, which shall be: <i>"Construction of Buildings"</i> .																					
7.1	<i>Subcontracting is not allowed</i>																					
10.3	<i>[Specify if another Contractor license or permit is required.]</i>																					
10.4	<p>The key personnel must meet the required minimum years of experience set below:</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;"><u>Key Personnel</u></th> <th style="text-align: center;"><u>General Experience</u></th> <th style="text-align: center;"><u>Relevant Experience</u></th> </tr> </thead> <tbody> <tr> <td>1. Project Manager</td> <td style="text-align: center;">3 years</td> <td style="text-align: center;">3 years</td> </tr> <tr> <td>2. Project Engineer</td> <td style="text-align: center;">3 years</td> <td style="text-align: center;">3 years</td> </tr> <tr> <td>3. Materials Engineer</td> <td style="text-align: center;">3 years</td> <td style="text-align: center;">3 years</td> </tr> <tr> <td>4. Foreman</td> <td style="text-align: center;">3 years</td> <td style="text-align: center;">3 years</td> </tr> <tr> <td>5. Construction Safety Officer</td> <td style="text-align: center;">3 years</td> <td style="text-align: center;">3 years</td> </tr> <tr> <td>6. First Aider</td> <td style="text-align: center;">3 years</td> <td style="text-align: center;">3 years</td> </tr> </tbody> </table> <p>Attached the respective curriculum vitae and a photocopy of valid Professional Regular Commission (PRC) license of the key personnel. Construction Safety Officer and First Aider should have Certificate of Training.</p> <p>The key personnel may be assigned to a maximum of two (2) positions except for the Construction Safety Officer and First Aider.</p>	<u>Key Personnel</u>	<u>General Experience</u>	<u>Relevant Experience</u>	1. Project Manager	3 years	3 years	2. Project Engineer	3 years	3 years	3. Materials Engineer	3 years	3 years	4. Foreman	3 years	3 years	5. Construction Safety Officer	3 years	3 years	6. First Aider	3 years	3 years
<u>Key Personnel</u>	<u>General Experience</u>	<u>Relevant Experience</u>																				
1. Project Manager	3 years	3 years																				
2. Project Engineer	3 years	3 years																				
3. Materials Engineer	3 years	3 years																				
4. Foreman	3 years	3 years																				
5. Construction Safety Officer	3 years	3 years																				
6. First Aider	3 years	3 years																				
10.5	<p>The minimum major equipment requirements are the following: <u>Not Applicable</u></p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;"><u>Equipment</u></th> <th style="text-align: center;"><u>Capacity</u></th> <th style="text-align: center;"><u>Number of Units</u></th> </tr> </thead> <tbody> <tr> <td colspan="3">Supporting documents like proof of ownership, lease and/or purchase agreement shall be submitted within five (5) calendar days upon declaration of Lowest Calculated Bid. For lease agreement, such proof must include a certification of availability of equipment from the lessor for the duration of the Project.</td> </tr> </tbody> </table>	<u>Equipment</u>	<u>Capacity</u>	<u>Number of Units</u>	Supporting documents like proof of ownership, lease and/or purchase agreement shall be submitted within five (5) calendar days upon declaration of Lowest Calculated Bid. For lease agreement, such proof must include a certification of availability of equipment from the lessor for the duration of the Project.																	
<u>Equipment</u>	<u>Capacity</u>	<u>Number of Units</u>																				
Supporting documents like proof of ownership, lease and/or purchase agreement shall be submitted within five (5) calendar days upon declaration of Lowest Calculated Bid. For lease agreement, such proof must include a certification of availability of equipment from the lessor for the duration of the Project.																						
12	<i>[Insert Value Engineering clause if allowed.]</i>																					
15.1	<p>The bid security shall be in the form of a Bid Securing Declaration or any of the following forms and amounts:</p> <ol style="list-style-type: none"> a. The amount of not less than <i>Thirty Thousand Pesos (P 30,000.00)</i>, if bid security is in cash, cashier's/manager's check, bank draft/guarantee or irrevocable letter of credit; b. The amount of not less than <i>Seventy Four Thousand Nine Hundred Ninety Nine Pesos & 99/100 (P 74,999.99)</i> if bid security is in Surety 																					

	Bond.
19.2	Partial bids are not allowed.
20	<p>Additional Requirements to be submitted by the Bidder with the Lowest Calculated Bid within five (5) calendar days from receipt of the notice from the BAC:</p> <ol style="list-style-type: none"> 1. Certificate of Registration issued by the BIR 2. Latest Income and Business Tax Return filed and paid through the BIR Electronic Filing and Payment System (eFPS) <ul style="list-style-type: none"> - Latest Income Tax Return with proof of payment (BIR Form No. 1701Q or 1702Q) - Vat Returns (BIR Form No. 2550Q) or Percentage Tax Returns (2551Q) with proof of payment
21	<p>Additional contract documents relevant to the Project that may be required by existing laws and/or the Procuring Entity:</p> <ol style="list-style-type: none"> 1. Construction Schedule and S-curve 2. Manpower Schedule 3. Construction methods 4. Equipment Utilization Schedule 5. Construction Safety and Health Program approved by the DOLE 6. PERT-CPM or other acceptable tools of project scheduling 7. Certificate or Affidavit of Site Inspection 8. Contractor's All Risk Insurance (CARI)

Section IV. General Conditions of Contract

Notes on the General Conditions of Contract

The General Conditions of Contract (GCC) in this Section, read in conjunction with the Special Conditions of Contract in Section V and other documents listed therein, should be a complete document expressing all the rights and obligations of the parties.

Matters governing performance of the Contractor, payments under the contract, or matters affecting the risks, rights, and obligations of the parties under the contract are included in the GCC and Special Conditions of Contract.

Any complementary information, which may be needed, shall be introduced only through the Special Conditions of Contract.

1. Scope of Contract

This Contract shall include all such items, although not specifically mentioned, that can be reasonably inferred as being required for its completion as if such items were expressly mentioned herein. All the provisions of RA No. 9184 and its 2016 revised IRR, including the Generic Procurement Manual, and associated issuances, constitute the primary source for the terms and conditions of the Contract, and thus, applicable in contract implementation. Herein clauses shall serve as the secondary source for the terms and conditions of the Contract.

This is without prejudice to Sections 74.1 and 74.2 of the 2016 revised IRR of RA No. 9184 allowing the GPPB to amend the IRR, which shall be applied to all procurement activities, the advertisement, posting, or invitation of which were issued after the effectivity of the said amendment.

2. Sectional Completion of Works

If sectional completion is specified in the **Special Conditions of Contract (SCC)**, references in the Conditions of Contract to the Works, the Completion Date, and the Intended Completion Date shall apply to any Section of the Works (other than references to the Completion Date and Intended Completion Date for the whole of the Works).

3. Possession of Site

3.1 The Procuring Entity shall give possession of all or parts of the Site to the Contractor based on the schedule of delivery indicated in the **SCC**, which corresponds to the execution of the Works. If the Contractor suffers delay or incurs cost from failure on the part of the Procuring Entity to give possession in accordance with the terms of this clause, the Procuring Entity's Representative shall give the Contractor a Contract Time Extension and certify such sum as fair to cover the cost incurred, which sum shall be paid by Procuring Entity.

3.2 If possession of a portion is not given by the above date, the Procuring Entity will be deemed to have delayed the start of the relevant activities. The resulting adjustments in contract time to address such delay may be addressed through contract extension provided under Annex "E" of the 2016 revised IRR of RA No. 9184.

4. The Contractor's Obligations

The Contractor shall employ the key personnel named in the Schedule of Key Personnel indicating their designation, in accordance with **ITB** Clause 10.3 and specified in the **BDS**, to carry out the supervision of the Works.

The Procuring Entity will approve any proposed replacement of key personnel only if their relevant qualifications and abilities are equal to or better than those of the personnel listed in the Schedule.

5. Performance Security

- 5.1. Within ten (10) calendar days from receipt of the Notice of Award from the Procuring Entity but in no case later than the signing of the contract by both parties, the successful Bidder shall furnish the performance security in any of the forms prescribed in Section 39 of the 2016 revised IRR.
- 5.2. The Contractor, by entering into the Contract with the Procuring Entity, acknowledges the right of the Procuring Entity to institute action pursuant to RA No. 3688 against any subcontractor be they an individual, firm, partnership, corporation, or association supplying the Contractor with labor, materials and/or equipment for the performance of this Contract.

6. Site Investigation Reports

The Contractor, in preparing the Bid, shall rely on any Site Investigation Reports referred to in the SCC supplemented by any information obtained by the Contractor.

7. Warranty

- 7.1. In case the Contractor fails to undertake the repair works under Section 62.2.2 of the 2016 revised IRR, the Procuring Entity shall forfeit its performance security, subject its property(ies) to attachment or garnishment proceedings, and perpetually disqualify it from participating in any public bidding. All payables of the GOP in his favor shall be offset to recover the costs.
- 7.2. The warranty against Structural Defects/Failures, except that occasioned-on force majeure, shall cover the period from the date of issuance of the Certificate of Final Acceptance by the Procuring Entity. Specific duration of the warranty is found in the SCC.

8. Liability of the Contractor

Subject to additional provisions, if any, set forth in the SCC, the Contractor's liability under this Contract shall be as provided by the laws of the Republic of the Philippines.

If the Contractor is a joint venture, all partners to the joint venture shall be jointly and severally liable to the Procuring Entity.

9. Termination for Other Causes

Contract termination shall be initiated in case it is determined *prima facie* by the Procuring Entity that the Contractor has engaged, before, or during the implementation of the contract, in unlawful deeds and behaviors relative to contract acquisition and implementation, such as, but not limited to corrupt, fraudulent, collusive, coercive, and obstructive practices as stated in ITB Clause 4.

10. Dayworks

Subject to the guidelines on Variation Order in Annex "E" of the 2016 revised IRR of RA No. 9184, and if applicable as indicated in the SCC, the Dayworks rates in the Contractor's Bid shall be used for small additional amounts of work only when the Procuring Entity's Representative has given written instructions in advance for additional work to be paid for in that way.

11. Program of Work

11.1. The Contractor shall submit to the Procuring Entity's Representative for approval the said Program of Work showing the general methods, arrangements, order, and timing for all the activities in the Works. The submissions of the Program of Work are indicated in the SCC.

11.2. The Contractor shall submit to the Procuring Entity's Representative for approval an updated Program of Work at intervals no longer than the period stated in the SCC. If the Contractor does not submit an updated Program of Work within this period, the Procuring Entity's Representative may withhold the amount stated in the SCC from the next payment certificate and continue to withhold this amount until the next payment after the date on which the overdue Program of Work has been submitted.

12. Instructions, Inspections and Audits

The Contractor shall permit the GOP or the Procuring Entity to inspect the Contractor's accounts and records relating to the performance of the Contractor and to have them audited by auditors of the GOP or the Procuring Entity, as may be required.

13. Advance Payment

The Procuring Entity shall, upon a written request of the Contractor which shall be submitted as a Contract document, make an advance payment to the Contractor in an amount not exceeding fifteen percent (15%) of the total contract price, to be made in lump sum, or at the most two installments according to a schedule specified in the SCC, subject to the requirements in Annex "E" of the 2016 revised IRR of RA No. 9184.

14. Progress Payments

The Contractor may submit a request for payment for Work accomplished. Such requests for payment shall be verified and certified by the Procuring Entity's Representative/Project Engineer. Except as otherwise stipulated in the SCC, materials and equipment delivered on the site but not completely put in place shall not be included for payment.

15. Operating and Maintenance Manuals

- 15.1. If required, the Contractor will provide "as built" Drawings and/or operating and maintenance manuals as specified in the **SCC**.
- 15.2. If the Contractor does not provide the Drawings and/or manuals by the dates stated above, or they do not receive the Procuring Entity's Representative's approval, the Procuring Entity's Representative may withhold the amount stated in the **SCC** from payments due to the Contractor.

Section V. Special Conditions of Contract

Notes on the Special Conditions of Contract

Similar to the BDS, the clauses in this Section are intended to assist the Procuring Entity in providing contract-specific information in relation to corresponding clauses in the GCC found in Section IV.

The Special Conditions of Contract (SCC) complement the GCC, specifying contractual requirements linked to the special circumstances of the Procuring Entity, the Procuring Entity's country, the sector, and the Works procured. In preparing this Section, the following aspects should be checked:

- a. Information that complements provisions of the GCC must be incorporated.
- b. Amendments and/or supplements to provisions of the GCC as necessitated by the circumstances of the specific purchase, must also be incorporated.

However, no special condition which defeats or negates the general intent and purpose of the provisions of the GCC should be incorporated herein.

Special Conditions of Contract

GCC Clause	
2	<i>The Intended Completion Date is Thirty Five (35) Calendar Days.</i>
4.1	<i>The Start Date shall be seven (7) calendar days from the date of receipt of the Notice to Proceed.</i>
6	The site investigation reports are: <i>[list here the required site investigation reports.]</i>
7.2	<p><i>[Select one, delete the other.]</i></p> <p><i>[In case of permanent structures, such as buildings of types 4 and 5 as classified under the National Building Code of the Philippines and other structures made of steel, iron, or concrete which comply with relevant structural codes (e.g., DPWH Standard Specifications), such as, but not limited to, steel/concrete bridges, flyovers, aircraft movement areas, ports, dams, tunnels, filtration and treatment plants, sewerage systems, power plants, transmission and communication towers, railway system, and other similar permanent structures:]</i> Fifteen (15) years.</p> <p><i>[In case of semi-permanent structures, such as buildings of types 1, 2, and 3 as classified under the National Building Code of the Philippines, concrete/asphalt roads, concrete river control, drainage, irrigation lined canals, river landing, deep wells, rock causeway, pedestrian overpass, and other similar semi-permanent structures:]</i> Five (5) years.</p> <p><i>[In case of other structures, such as bailey and wooden bridges, shallow wells, spring developments, and other similar structures:]</i> Two (2) years.</p>
10	Dayworks are applicable at the rate shown in the Contractor's original Bid
11.1	The Contractor shall submit the Program of Work to the Procuring Entity's Representative within <i>[insert number]</i> days of delivery of the Notice of Award.
11.2	The amount to be withheld for late submission of an updated Program of Work is <i>[insert amount]</i> .
13	The amount of the advance payment is <i>15% of the total contract price.</i>
14	<i>[If allowed by the Procuring Entity, state:]</i> Materials and equipment delivered on the site but not completely put in place shall be included for payment.
15.1	<p>The date by which operating and maintenance manuals are required is <i>[date]</i>.</p> <p>The date by which "as built" drawings are required is <i>upon completion of the project.</i></p>
15.2	The amount to be withheld for failing to produce "as built" drawings and/or operating and maintenance manuals by the date required is <i>[amount in local currency]</i> .

Section VI. Specifications

Notes on Specifications

A set of precise and clear specifications is a prerequisite for Bidders to respond realistically and competitively to the requirements of the Procuring Entity without qualifying or conditioning their Bids. In the context of international competitive bidding, the specifications must be drafted to permit the widest possible competition and, at the same time, present a clear statement of the required standards of workmanship, materials, and performance of the goods and services to be procured. Only if this is done will the objectives of economy, efficiency, and fairness in procurement be realized, responsiveness of Bids be ensured, and the subsequent task of bid evaluation facilitated. The specifications should require that all goods and materials to be incorporated in the Works be new, unused, of the most recent or current models, and incorporate all recent improvements in design and materials unless provided otherwise in the Contract.

Samples of specifications from previous similar projects are useful in this respect. The use of metric units is mandatory. Most specifications are normally written specially by the Procuring Entity or its representative to suit the Works at hand. There is no standard set of Specifications for universal application in all sectors in all regions, but there are established principles and practices, which are reflected in these PBDs.

There are considerable advantages in standardizing General Specifications for repetitive Works in recognized public sectors, such as highways, ports, railways, urban housing, irrigation, and water supply, in the same country or region where similar conditions prevail. The General Specifications should cover all classes of workmanship, materials, and equipment commonly involved in construction, although not necessarily to be used in a particular Works Contract. Deletions or addenda should then adapt the General Specifications to the particular Works.

Care must be taken in drafting specifications to ensure that they are not restrictive. In the specification of standards for goods, materials, and workmanship, recognized international standards should be used as much as possible. Where other particular standards are used, whether national standards or other standards, the specifications should state that goods, materials, and workmanship that meet other authoritative standards, and which ensure substantially equal or higher quality than the standards mentioned, will also be acceptable. The following clause may be inserted in the SCC.

Sample Clause: Equivalency of Standards and Codes

Wherever reference is made in the Contract to specific standards and codes to be met by the goods and materials to be furnished, and work performed or tested, the provisions of the latest current edition or revision of the relevant standards and codes in effect shall apply, unless otherwise expressly stated in the Contract. Where such standards and codes are national, or relate to a particular country or region, other authoritative standards that

ensure a substantially equal or higher quality than the standards and codes specified will be accepted subject to the Procuring Entity's Representative's prior review and written consent. Differences between the standards specified and the proposed alternative standards shall be fully described in writing by the Contractor and submitted to the Procuring Entity's Representative at least twenty-eight (28) days prior to the date when the Contractor desires the Procuring Entity's Representative's consent. In the event the Procuring Entity's Representative determines that such proposed deviations do not ensure substantially equal or higher quality, the Contractor shall comply with the standards specified in the documents.

These notes are intended only as information for the Procuring Entity or the person drafting the Bidding Documents. They should not be included in the final Bidding Documents.

Specifications

A. GENERAL REQUIREMENTS

TS-1 General

1.1 Provision

The Contractor shall perform all required scope of works for the National Meat Inspection Service (NMIS).

1.2 Drawings and Specification

Drawings and specification are intended to complement each other, so that of anything is shown on the drawings, but not mentioned in the specifications, or vice versa, it is to be furnished and built as though specifically set forth in both. If any discrepancies occur in the drawings or specification, the same shall be referred to the Engineers assigned in the project before proceeding with the work. The Engineer's decision on such discrepancies shall be final provided that the said discrepancies will not incur any additional amount and will not sacrifice the structural integrity of the project.

1.3 Large scale drawings shall have preference over smaller scale drawings and figured dimensions shall have preference over scaled dimensions.

1.4 The Engineer may, during the progress of the work furnish additional drawings, specifications and instructions as may be necessary, for the proper and adequate implementation of the work. In this case, the Contractor shall make his work conform to all such drawings, specifications and instruction. Such drawings specifications and instruction shall be deemed to the part of the Contract Documents.

1.5 Minor Change The Engineer shall have also authority to direct minor changes in the work provided that there will be no adjustment in the contract cost and the contract schedule. Such changes shall be binding on the Owner and the Contractor.

1.6 Applicable Standard and Codes The following terms listed or referred herein or indicated in the drawings are to be used for reference and latest edition of the publication to the date of these specifications shall apply.

ASTM - American Society for Testing and Materials

ACI - American Concrete Institute

AISC - American Institute of Steel Construction

ANSI - American National Standard Institute

CRSI - Concrete Reinforcing Steel Institute

AWS - American Welding Society

ASSHTO - American Association of State Highway and Transportation Office

1.7 The Contractor may use local standards and codes equivalent to those referred in this Technical Specifications.

PS - National Standard

NBC - National Building Code of the Philippines

NSC - National Structural Code of the Philippines

PCP - Plumbing Code of the Philippines

PEC - Philippine Electrical Code

TS-2 Construction Schedule and Execution Plan

The Contractor shall prepare and submit to the Engineer for reference a construction schedule and day to day activity plans of implementation. The contractor shall also submit the list/names of his labor force with their designations.

TS-3 Permit

The Contractor shall, prior to the start of work, ensure that the needed building permit is being process or approve by municipality concerned.

TS-4 As-Built Drawings and Construction Log Book

The Contractor shall prepare and submit the as-built plans of the project he is undertaking including the construction logbook used in the implementation prior to the release of the final payment.

TS-5 Construction Photograph

The contractor shall prepare and submit all require photographs of progress and completion of construction.

TS-6 Sampling and Testing

Sampling and testing of materials shall be done by and at the expense of the contractor. All tests required shall be performed at the approved laboratories. The materials represented by the sample shall not be considered acceptable until the required tests have been performed and the results have been found to conform with the requirements of the plans and specifications.

TS-7 Soil Investigation and Testing

The Contractor shall, prior to start of work conduct soil investigation and testing to determine the allowable bearing capacity. At least two (2) boreholes with a minimum depth of 15.0 meters each shall be done. The specimen shall be tested at the approved laboratories. The Contractor shall furnish the Engineer a copy of the result of the soil testing. If the soil investigation and testing is found unnecessary, the provisional sum in the bill of quantities shall automatically be deducted from the contract price.

B. MASONRY

TS-8 General

The scope of work covers the furnishing of all labor, equipment and materials for the erection of walls made of non load bearing, 100mm and/or 150mm thick concrete hollow blocks.

TS-9 Materials

9.1 All materials supplied under the Contract shall conform to the requirements of the Philippine Standard Association and the National Structural Code of the Philippines, Volume 1.

9.2 Recommended strength of CHB for both external and internal use of the building shall not be less than 450 psi.

9.3 Portland cement mortar for laying concrete hollow blocks shall consist of one (1) part Portland cement, and three (3) parts sand.

9.4 Mortar materials shall accurately measure by volume and thoroughly mixed until evenly distributed throughout the batch. Unless otherwise approved by the Engineer, mixing by batch shall be by mechanical mixer of not less than two (2) minutes per batch.

9.5 Masonry materials shall be handled with care to prevent chipping and breakage. Masonry units shall be stacked on platform and covered or stored in any other approved manner that will protect these materials from contact with the soil and exposure to the weather. Cement shall be stored off the ground under water tight cover and away from sweating walls and other damp surfaces until ready for use. Damage or deteriorated materials shall be removed from the premises.

9.6 All steel reinforcement for masonry works shall be in accordance with the approved plan and details as shown in the drawings.

TS-10 Methods of Construction

10.1 All masonry units shall be laid plumb, levelled and accurately spaced. Wall intersection shall be toothed alternately. End of walls shall be in vertical line.

10.2 All masonry units shall be wetted before laying. The blocks shall be laid in mortar bedding and such a way that no cracks are formed between the blocks and the mortar at the time the block is placed.

10.3 The blocks shall be adjusted to its final position while mortar is still soft and plastic to insure a good bond.

10.4 The position of the concrete block shall not be shifted after the mortar has stiffened.

10.5 All horizontal and vertical joints must be filled solid with 3/8-inch (9.5mm) thick mortar unless otherwise specified or detailed on the drawings. Any patching necessary to fill the joints should be completed.

10.6 All vertical masonry wall reinforcement shall be anchored to concrete wall

footing and roof beam. Likewise horizontal reinforcement should be anchored to column bars and should be tied where it meets any vertical masonry wall reinforcement.

10.7 Filling of CHB shall be carried out in stages not exceeding 3 courses at a time and the concrete properly compacted without disturbing the block-work.

10.8 The filler concrete shall be stopped at a level about thirty six (36) mm (1 ½) below the top of the blocks laid when filling on concreting is to be stopped for more than one (1) hour.

10.9 All the completion of the work, all excess mortar on masonry surfaces and mortar spilled on floor slabs shall be removed.

C. METAL WORKS

TS-11 General

11.1 Steel truss work includes furnishing all materials, tools and equipments and performs labor services required to complete fabrication and erection of all structural steel and miscellaneous steel like structural steel trusses, purlins, structural steel frames and connection system.

11.2 The contractor shall be responsible for the accurate location of all steel work including items used to attach materials to other parts of the work based on plans.

11.3 The contractor shall see to it that any and all items of work which are to be built into works of other trades are installed at the proper time

11.4 The contractor shall notify the Engineer if the steel work shall be fabricated in a shop other than the site, so that arrangements in the inspection of the delivered materials and in the fabrication of the steel work.

11.5 Complete and detail fabricator tolerances and erection including details of all connections and anchorage shall be approved by the Engineer.

TS-12 Materials

12.1 All materials and workmanship should conform to the requirements of the American Institute of Steel Construction (AISC), "Specification for Design, Fabricator and Erection of structural Steel for Buildings", as amended to date or as may be specifically modified by the drawings.

12.2 All mild steel angles, flat bars, square bars, channels, U, and other sections. C purlins that may be used shall be with stiffened flange for built-up, rigid frame roof beam.

12.3 All standard structural grade level rods with turnbuckles shall be used if applicable.

12.4 All structural steel plates and shapes shall conform to ASTM Designation A36 with a specified yield point of 36,000 psi.

12.5 Sizes, shape and design of all mild steel sheets or plates shall be as indicated in the drawings.

12.6 All welding electrode shall conform to E60 series of ASTM Specifications ZA-233 and AWS Specifications A5.0 and A5.5

12.7 All bolts to be used shall conform to the specifications for low carbon steel.

12.8 All red lead paint shall be "Boysen" or its approved equivalent.

TS-13 Installation and Methods of Construction

13.1 All welding technique, the appearance and quality of welds made and methods shall be based to the requirements of the Standard Code for Welding in Building Construction for the American Welding Society (AWS) as adapted by the Department of Public Works and Highways.

13.2 All surfaces to be welded shall be free from loose scale, slag, rust, grease, paint and any other foregoing material except that mild scale which withstands vigorous wire brushing may remain. Joint surfaces shall be free from fins and tears.

13.3 All cut edge shall be subject to substantial stress to have weld metals deposited of them be free from gouges and must be removed grinding.

13.4 Never exceed the separation between laying surfaces of lap joints and butt joints on a backing structure by 1.58mm (1/16 inch).

13.5 Bring the fit of joints at contact surfaces which are not completely sealed by welds, close enough to exclude water painting.

13.6 Distortion and shrinkage in all joining parts of structure or built-up members must be avoided. If possible, avoid high residual stress in the closing welds of a rigid assemble and all welds in compression elements.

13.7 In the fabrication of cover plated beams and build-up members, all shop splices in each component part before such component part shall be welded to the other parts of the member splicing not more than three sub-sections.

13.8 Exposed surfaces of welds shall be reasonably smooth and uniform and shall project not more than 1.58 mm (1/16 inch) above the surfaces joined. No finishing or grinding shall be required except when clearances or fit of other items is required in the drawings.

13.9 All structural members of single rolled shape and built-up members fabricated riveting or welding, unless otherwise specified, be straight within the tolerances allowed by ASTN Specification A6.

13.10 Fabrication shall be performed with special care and necessary straightening to maintain the structural condition of the structures.

13.11 Clean all steel work specified for painting by hand or other methods approved by the Engineer.

13.12 Do not paint any steel work that is to be encased in concrete. Clean all greased or with solvent cleaners. Removed dirt and foreign materials thorough

sweeping with a fiber brush. Contact surfaces shall be cleaned but not painted.
13.13 Machine finished surfaces shall be protected against corrosion by a rust-inhibiting coating that can easily be removed prior to erection or which has characteristics that make removal unnecessary to erection.

13.14 The contractor shall use special care in unloading, handling and erecting all the steel to avoid, banding, twisting or otherwise distorting the steel members. The erector shall handle the materials in such a way as to minimize the damage to the shop-coated of paint. The contractor shall plan and execute the erection in such a way so that the close fit and neat appearance of the joints and the structure, as a whole, will not be impaired. If temporary braces or erection clips are employed, care shall be taken to avoid any unsightliness upon removal. Tack welds shall be ground smooth and holes shall be filled with weld metal or Contractor shall submit to the Engineer the sequence of erection for approval.

13.15 The frame of the steel roof framing shall be carried up true and plumb and temporary bracing shall be introduced wherever necessary to take care of loads to which the structure may be subjected, including equipment and the operation of the same. Such bracing shall be left in place as long as may be required for safety. Wherever piles of materials, erection equipments or other loads are varied during erection proper provisions shall be made to take care of stresses resulting from such loads.

13.16 No riveting, permanent bolting or permanent welding shall be done until the structure has stiffened with resulting stresses and properly aligned.

13.17 Any shop paint on surfaces adjacent to joints to be field welded shall be wire brushed, to reduce the paint film to a minimum.

13.18 Structural steel truss members shall be aligned, plumbed straight in fabrication, welding and installation.

13.19 The structural steel shall be fabricated, handled and crated as per specifications and conformity with the American Institute of Steel Construction (AISC) Specification for the design, fabrication and erection of the structure steel for buildings.

13.20 After erection, all unpainted areas including any marred or damaged surfaces shall receive one coat of same inhibitory painting.

D. WOOD WORKS

TS-14 General

14.1 The works consist in furnishing all materials, plant, labor, equipment and all other items specified in the drawings and in the specifications. It also includes all operations necessary for the completions of all carpentry works.

14.2 Lumber shall be of the approved quality, of the respective kinds required for the work, well seasoned, thoroughly dry, straight and free from large, loose or unsound knots, saps, shakes, or other imperfections which may affect its strength, durability and appearance.

14.3 Framing lumber (if applicable) including trusses, rafters, purlins, and girts shall be of the rough dimension shown on the drawings). Any planned lumber supplied shall have a finish size than the rough dimensions specified on the drawings.

14.4 All cutting, faming, fitting and other rough lumbers necessary for the accommodation and completion of the work shall be provided.

TS-15 Protection and Storage

15.1 Shall be protected and kept under cover both in transit and at the job site, and shall be carefully in piled off the ground and be insured of proper drainage, ventilation, and protection from the weather.

15.2 All surface wood framework and other wood members coming in contact with or embedded in concrete shall be painte4d with two (2) coat of asphalt applied hot or coal tar.

15.3 The contractor shall protect all finish woodwork from injury after it has been set in place until the completion and final acceptance of work.

TS-16 Substitution of Lumber

Any lumber intended to be used may be substituted if the substitute belongs to the same group of the kinds specified. However, a deducted may be considered if the unit cost of the substitute is lower than that of the unit cost as stated in the contract. Any substitution must be subject to the approval of the Engineer.

TS-17 Materials

17.1 When the type and kind of materials of lumber for this purpose is not specified in the drawings and details the following shall be used:

a. Guijo or Apitong – for all door jambs, window jambs, headers and transom bars; wood plates and all other wood coming in contact with concrete or masonry.

b. Tanguile or Red Lauan - for all ceiling framing, studding and partitions (applicable to project using lumber)

c. Plywood – shall be 6 mm (1/4 inch) thick for all ceiling, marine type for eaves while ordinary type for inside ceiling. If applicable, 19 mm (3/4 inch) thick shall be used for cabinet and its doors.

TS-18 Methods of Construction

18.1 All framing and other rough carpentry shall be fitted closely and care4fully to the required lines and levels, and shall be secured in place in a rigid substantial manner.

18.2 Door jambs indicated on the drawings, in contact with concrete shall be anchored using 4-inch common wire nails spaced not more than 200 apart, all around the contact surface.

18.3 Fastening, except where bolts are shown on the drawings shall be common wire nails.

18.4 Nails shall be of the proper size, and care shall be taken so as not split the wood members.

18.5 All dimensions shall be verified on the site before fabricating joinery items. All joints shall be accurately and cleanly formed to conform to the required details. All items of work shown on the drawing shall be done by the Contractor in accordance with good workmanship practice and in accordance with the best reasonable interpretation of the plans and related specification. Use Wellwood or other approved water-resistant glue for assembly of materials and other joinery.

E. THERMAL AND MOISTURE PROTECTION

TS-19 General

This includes the supply all labor, plant, materials, equipment, and other facilities required to complete all roofing work as shown on the drawings and specified herein. Work shall be done by trained and experienced workmen who are completely familiar with the materials and the recommended methods of installation.

TS-20 Materials

20.1 GA. 26, corrugated, manufacturer pre-painted long span G.I. Roofing shall be used and all bended accessories such as ridge rolls, end flashing, side flashings and corner flashings shall be GA. 24. Preformed pre-painted G.I. materials and delivered to site free from any damages.

20.2 Cement from concreting works, chemical solutions, paint, welding sparks, nails and iron tools should not be allowed to drop on, extend to or rust away at the roof since removal or scraping of materials later could damage the roof's coating, roof traffic should be minimized. When crossing the roof area, walking should be conducted along roof frame locations, along overlaps or on wooden planks laid over the roof panels.

TS-21 Methods of Construction

21.1 Roofing sheets shall laid and shoulder start opposite the direction of the prevailing monsoon winds, lay and install the first panel with the female rib (side edge without over-bend) facing the area to be roofed. Overlap the male rib (side edge with over-bend) of the next panel on the female rib of the previous panel. Roofing sheets can be fastened by means of stove bolt with aluminum rubber washers or teks screw with rubber washer. Manufacturers' specification maybe acceptable to as directed by the Engineer.

21.2 Roof mounting strip/connector or tight frame shall be FB2.3 x 30 galvanized steel sheet and shall be fastened to the purlins by full weld or water head teks screw or as directed by the Engineer. Ridge rolls and other flashings shall be attached to the roofing sheets by means of rivets or screw.

F. DOORS AND WINDOWS

TS-22 General

22.1 The work includes the furnishing of materials, equipment, methods and in performing all operation for all wood doors and windows, complete in accordance with the plans and this specification.

a. All lumbers for door and window frames shall be kiln-dried and approved

grade lumber as specified in the technical specifications. All doors and windows shall be of the type done in accordance with the details as shown on the drawings. Refer to the schedule of doors and windows.

b. The Contractor shall be responsible for the proper execution and exactness of dimensions. Shop drawings shall be presented by the Contractor to the Engineer for review and checking prior to production.

TS-23 Storage and Protection

Wood doors, windows and frames shall be protected against damage and dampness. The horns on doors and window frames should be only at the time of installation. Doors and windows shall be stored under cover in a well-ventilated building where they will not be exposed to extreme changes of humidity.

TS-24 Materials

24.1 Frames shall be of the design, size and thickness indicated on the drawings. Wood and window frames in masonry or concrete walls shall be nailed as indicated on the drawings.

24.2 Door hardware and accessories shall be of the design and patterns that will prevent the infiltration of water through its operating parts.

24.3 Flushed Type Door studs shall be of tangile. Kiln-dried. Use 6mm (1/4") thick marine plywood covering on both sides of door, and shall be of commercial standard. Design and details shall be as indicated in the drawings.

24.5 Hinged door shall be hung plumb, and fitted accurately allowing three (3) mm clearance at the jambs. Use four (4) butt hinges for each panel or hinged door as shown in the drawings.

24.6 Movable jalousie shall be lever type aluminum frame mechanism. Type and brand shall be subject to the approval of the Consultant. Glass blades for jalousie shall not be less than 6mm (1/4") thick. Glass shall be correctly cut to its net dimension on sides and both ends and shall be free from foam, cracks, deformation and other defects. Edges of the glass shall be well chamfered and other performance as maybe directed by the Engineer.

TS-25 Hardware

25.1 General

a. The work includes all rough hardware, required for the completion of the work, including nails, bolts, screw, etc., and shall provide and fit in place all finishing hardware hereinafter specified put in the proper manner with screws to match the finishes.

All hardware shall be installed in a neat, acceptable manner, following manufacturer's instruction. Except as indicated or specified otherwise, fasteners furnished with the hardware shall be used to fasten hardware in place. After installation, protect hardware from paint, stain, blemishes and other damage until acceptance of the work. All hardware shall be adjusted properly and checked in the presence of the Engineer and hinges, lock and other items shall be operating properly. After all hardware is checked, keys shall be

tagged, identified and delivered to the Engineer. All errors in cutting and fitting, and all damage to adjoining work shall be corrected, repaired and finished as directed by the Engineer.

G. FINISHES

TS-26 Plastering

26.1 General

The work includes the furnishing of materials, equipment, method and the labor necessary to complete all plastering in accordance with the drawings and specified herein.

26.2 Materials

All materials specified herein shall be subject to the specification of manufacturers and to the approval of the Engineer.

a. Portland Cement shall conform to ASTM C-150, Type 1.

b. Sand shall be hard well washed, clean and free from deleterious materials conforming to ASTM C-40.

c. Lime shall be hydrated lime with the requirement that calcium oxide (CaO) and the magnesium oxide (MgO) shall not exceed eight (8) percent by weight calculated.

d. Water shall be potable, clean and free from organic matter, acids and alkalis.

26.3 Delivery and Storage Manufactured materials shall be delivered in the original unbroken packages and containers

bearing the name and brand of the manufacturer. Cement materials shall be kept away from the sweating walls and damp surfaces until ready for use. Damage or deteriorated materials shall be removed from the premises.

26.4 Mixture

Plaster shall be thoroughly mixed with the proper amount of water until uniform in color consistency. Tampering will not permit and all plaster that has begun to stiffen shall be discarded. Cement mortar shall be a three (3) coat application. Each coat shall be proportional as follows: one (1) part Portland Cement, three (3) parts sand and one fifth part lime putty.

26.5 Methods of Construction

a. Surfaces to receive plaster shall be cleaned of all loose particles, dust, cracks and other foreign matter. Before the plastering work is started, masonry surfaces shall be wetted thoroughly with fog, spray of clean water to produce a uniformly moist condition. Corner beads, screeds and other accessories shall be checked carefully for alignment before work is started.

b. The coat shall be applied with sufficient pressure to fill the grooves in hollow blocks or concrete to prevent air pockets and secure a good bond. The coat shall be lightly scratched and broomed. Each coat of cement plaster shall be kept moist for four (4) hours after application and then allowed to dry.

c. Finish and final coat shall not be applied until the first coat has seasoned for 7 days.

Just before the application of the finish coat, the first shall again be evenly

moistened with a fog coat; the first shall be floated first to a true and even surface the troweled in a manner that will force the sand particles down into the plaster. Plastered surfaces shall be smooth and free from rough areas, troweled marks, checks and blemishes. Thickness of plaster shall be 9mm (3/8") on vertical concrete and on masonry.

d. On wall finishing, exterior and interior finishes shall be plain cement plaster finish or whatever is specified on the drawing.

e. Toilet wall finishes shall be vitrified glazed ceramic tiles wainscoting. (Refer to ceramic tile work for detailed information).

f. Plastering work shall be finished level, square and true within a tolerance of 5 millimetre in 4.8 meters without cracks, wakes, blisters, pits, projections and other imperfections. Plaster work shall be formed carefully around corners, contours and well-up to screeds. Care shall be taken to prevent sagging and drooping of applications. There shall be no visible junction marks, in the finish coat where one day's work adjoins the other.

g. Upon completion of the building and when directed, all loose, cracked, damaged, or defective plastering shall be cut out and re-plastered in a satisfactory and approved manner. All pointing and patching of plastered surfaces, and plaster work abutting of adjoining any other finish work, shall be done in neat and acceptable manner. Plaster droppings shall be removed from all surfaces. Exposed plastered surfaces shall be left in a clean unblemished condition ready to receive paint or other finish. Protective covering shall be removed from floors and other surfaces, and all rubbish and debris shall be removed from the building.

TS-27 Materials

27.1 General

Tile work shall not be started until all installation for plumbing and electrical work has been completed and tested.

27.2 Materials

Manufactured materials shall be delivered in the manufacturer's original unbroken packages or containers that are labelled plainly with the names and brands.

a. Floor tiles at toilets shall be unglazed vitrified ceramic tile, 300mm x 300mm x 6.4mm (12" x 12" x 1/4") per piece of tile manufactured by approved brand.

b. Wall tiles and counter shall be glazed vitrified ceramic tiles, 300mm x 300mm x 6.4mm (12" x 12" x 1/4") per piece of tile manufactured by approved brand.

c. Trimmers and moldings shall be bright mat glazed to fill the sizes and match with the finish of the wall tiles.

d. Washing counter tiles or science laboratory shall be 300mm x 300mm vitrified glazed tiles and shall be acid resistant manufactured by approved brand.

27.3 Construction Methods

a. Wall tiles shall cover walls and partitions to nominal height as indicated on the drawings. Finish of wall and wainscot tiles shall be uniform for all toilet rooms.

b. Mortar for setting wall tile and floor tiles shall consists of one (1) part Portland cement, 1-1/4 part lime putty and three (3) parts sand by volume.

c. All tile bathes to be thoroughly mixed before placing to balance out any manufacturer's variation in color and texture.

d. Glazed wall tile shall be thoroughly soaked in clean water before being set.

e. Tiles shall be firmly secured in placed. Joints shall be well filled, lines kept straight

and true, and finished surfaces brought to a true plane. Setting beds of floor tiles shall be thick enough to bring the tops of the tiles to the finish slope or levels indicated. Wall filled tiles shall be set with horizontal and vertical straight line joints, except as indicated otherwise, intersection and returns shall be perfectly formed. Cutting and drilling of tiles shall be neatly done without damaging the surfaces of the Tiles.

TS-28 Floor Hardener

28.1 Properties

Floor Hardener is produced from highly graded granite/quarts aggregates and special chemical additives to provide extremely abrasion resistant surfaces protect the surface from gas, oil and chemical attack and provide non skid, anti-slip properties. Surfaces treated with floor hardener are capable of withstanding high point impacts and stresses.

38.2 Applications

For indoor and outdoor use, Floor Hardener is pre-mixed with Portland cement ex-factory. Surface armoring is achieved by spreading evenly on freshly screeded concrete as follows:

o Light Traffic : 3 kg/sqm o Medium Traffic : 4 kg/sqm o Heavy Traffic : 5 kg/sqm

Typical Method of Application:

1. Follow good concreting practice when laying base slab.
2. Smooth and close the surface of concrete with wood float to ensure an even and dense surface. Remove any excess water or laitance from the surface of the slab using a soft broom.
3. Spread aggregate and cement mix in two equal stages evenly over the surface of the concrete. The first application is made as soon as the floor is firm enough so that the aggregates do not sink.
4. Wood float or trowel to compact the first layer.
5. Spread the second layer approximately 1 or 2 hours after the first application.
6. Smooth lightly with a steel trowel taking extra care to ensure that the aggregates are not embedded under the substrate surface.
7. When firm, steel trowel again to bring the surface to a perfect finish again making
sure that the aggregates are not buried beneath the surface.
8. To produce a non-slip finish, trowel in a sweeping circular motion to produce slight ridges.

TS-29 Painting

29.1 General

The work under this section of this specification shall include the furnishing of all materials, labor, tools and other facilities necessary to complete all painting of all surfaces throughout the interior and exterior of the building except as otherwise specified. Before paint application, the contractor shall inspect all surfaces to be painted and all defects shall be remedied. For concrete surfaces all dirty matter shall be removed by scrubbing affected surfaces with a solution of muriatic acid and water (add a half to pint of acid to a gallon of water), and rinse with a clear water to allow to dry thoroughly. All nail holes, cracks or open joints shall be puttied, caulked, or grouted.

29.2 Materials

- a. All paint materials shall be delivered to the jobsite in original containers with seals unbroken and labels intact. Materials that are damaged during delivery shall be replaced by the contractor at his own expense. With the exception of ready-mixed materials in original containers, all mixing shall be done at the jobsite.
- b. All paints shall be applied in accordance with the manufacturer's printed instructions.
- c. All materials called for under this section of specifications shall be as manufactured by "Boysen" or approved equal.

29.3 Color and Samples

- a. Color coordinates and samples shall be submitted by the Contractor to the engineer to review and approval. No painting shall be done without first securing prior approval of submitted color samples, schedule and coordinates.
- b. Tinting or matching of colors shall be done under the supervision of the Engineer. If required, each color and finish shall be prepared in advance, with the materials specifications for the approval of the Engineer. "Off color selected" shall be understood of all colors specified therein.

29.4 Paint Application and Methods

- a. All concrete and masonry and other surfaces shall be in a condition necessary to receive satisfactory paint finish. All nail holes, cracks or open joints shall be puttied, caulked, or grouted. Putty, when necessary shall be applied with a knife after a prime coat has been applied.
- b. Scrape off loose mortar surface contaminants, then steel brush to remove chalk, dust, dirt, and surface deposits.
- c. All concrete masonry surface must be thoroughly neutralized either by brush or spray with a solution four (4) pounds of zinc sulphate to each gallon of water. Treated surface shall be treated with litmus paper to ascertain that alkalinity is removed, otherwise a second washing with the solution shall be applied. After drying, all crystals on the neutralized surface must be brushed off before applying the priming coat.
- d. All mill work and other wood works where painting is required shall be sandpapered brush, to remove dust, before application of the primer. Resulting

voids, nail holes, cracks shall be filled with approved putty. Touch up all knots, pitch streaks and sappy spots with approved sealer.

e. Scrape off rust from the surface with steel brush and sweep to remove dust, dirt and all surface contaminants. Oil and grease adhering to the surface may be removed by washing affected surface with soap and water. Holes shall be patched-up with soldering lead.

f. No exterior painting shall be done in rainy, damp weather or until surfaces are thoroughly dry. No interior painting or finishing shall be permitted until building has been thoroughly dried-out.

g. Finish shall be applied only over the preceding coats which are hard and dry. Finish shall be evenly and smoothly applied in thin but covering coats, and shall be free from runs, sags or crawlings.

h. The use of heavy brush is required. Paints shall be thoroughly stirred so as to have the pigment evenly in suspension while paint is being applied. Except where other is noted or specified, all paint shall be applied in three (3) coats.

Wood surfaces:

i. Painted doors, jambs, cabinets, shelves (semi-gloss finish)

1st coat – lacquer primer surface

2nd coat – lacquer primer surface

3rd coat – semi-gloss lacquer surface

ii. Plain painted surfaces such as walls, partitions and ceilings

1st coat – interior sealer and primer

2nd and 3rd coat – flat wall enamel

i. Exterior concrete wall and cement plaster – all exterior concrete shall be painted except as otherwise specified on the drawings.

i. 1st coat – acrytex primer;

ii 2nd and 3rd coat – acrytex topcoat (semi-gloss)

29.5 Cleaning

Upon completion of the work the Contractor shall remove from the building all used materials, debris, and all paint spots on the floor, washing of window glass, hardware fixture, etc. All work performed under this section shall be left clean and acceptable to the Engineer.

29.6 Guarantee

The Contractor shall guarantee his work for a period of one (1) year, when using the materials specified by the Engineer. The Contractor shall repair all defects due to faulty material or workmanship caused by him without any additional compensation for the period specified.

TS-30 Miscellaneous

30.1 General

The work under this section of specification shall include the furnishing of all materials, labor, tools, and other facilities necessary to complete production and installation of the sign and signboards as indicated herein.

30.2 Materials

The materials for the building name plate shall be stainless steel metal sheet 1.587mm (1/16") thick or its commercial gauge equivalent and shall bear the inscriptions stated per attached sketch. The name plate shall be anchored by an expansion bolt directly to the concrete as directed by the Engineer. The size, dimension and material type shall be subject to the approval of the Owner upon presentation of samples.

The materials for the toilet signs shall be of acrylic plastic sheets 4.762mm (3/16") thick or its commercial thickness equivalent and shall bear the sign/inscriptions stated as per sketch. The size and dimension shall be as subject to the approval of the Engineer.

H. MECHANICAL WORKS (PLUMBING)

TS-31 General

31.1 The Contractor shall furnish all labor, materials and equipment necessary to complete and make functional the sanitary, drainage and water supply system. The Owner shall provide necessary drilling of water well and shall yield substantial quantity/volume of water needed to have a functional water supply system to project site either in rainy or dry seasons. The Owner shall likewise arrange/secure consent/approval of tapping to existing water line if necessary or requested by authorities concerned.

31.2 All works shall comply with the provisions of the Philippine National Plumbing Code, MWSS regulations, DPWH guidelines and all other codes and ordinances other local authorities having jurisdiction over the project.

31.3 "Roughing-in" for all pipes and fixtures shall be carried along with the building construction. Correct location for the pipes shall be kept in the walls and floor as specified in the plans.

TS-32 Materials

32.1 All materials must bear the trademarks reference of the manufacturers. The Contractor shall furnish the Engineer with the original and copies certified of origin of materials to be used.

32.2 Soil, waste, Vent Pipes and Fittings shall be made of unplasticized polyvinyl chloride (UPVC) Schedule 40 or whatever indicated in the drawing and shall be manufactured by "Neltex" or its approved equivalent in property certificated by Bureau of Product Standard.

32.3 Water pipes and fittings shall be made of galvanized iron pipes (6.1) – schedule 40 or whatever indicated in the drawings and shall be approved equal in property certificated by Bureau of Product Standard. Water pipes requiring installation of PVC or as indicated in the drawings shall use "Modex Blue" or approved equivalent.

32.4 Cleanouts shall be the same as pipe diameter, installed in connection with UPVC hubs and spigot pipes consist of a long sweep quarter extended as indicated in the drawings. An extra heavy cast brass ferrule with countersink trap screw cover caulked into hub if the fittings shall be flushed with the floor.

32.5 Floor drains shall be nickel or chrome plated or approved equal, local

manufactured.

32.6 Gate valves shall be brass or bronze solid wedge type with screwed ends, or its equivalent as approved by the Engineer.

32.7 Hose bib shall be brass with male inlet threads hexagonal shoulders and hose connection. Hose bib and faucet shall be of the approved type, locally manufactured.

32.8 Plumbing fixtures and equipment shall be properly identified to illustrate the quality and design of fixture that will be required. All fixtures shall have supply line with cut-off valves having chromium finish and shall be as manufactured by Philippine Standards as follows.

32.9 Water closet shall be of floor mounted tank type complete with all fittings. Color shall be in White (For handicapped only)

32.10 Lavatory shall be complete with necessary fittings. Color is white.

32.11 Laboratory sink shall be 100mm thick R.C. slab with glazed ceramic tiles.

32.12 Provide traps at every plumbing fixture and other equipment requiring connection to the drainage system.

32.13 Lavatory Counters and Cabinets shall be 100mm thick R.C. slab with glazed ceramic tiles counter top.

32.14 Adapters shall be used to join pipes, fittings of different types and sizes and different combination approved by the Engineer.

TS-33 Methods of Construction

33.1 All work shall be done by skilled worker only under the supervision of a master plumber. Contractor shall perform the work in accordance with good workman like practice to the satisfaction and approval of the Engineer.

33.2 On completion of the sanitary, drainage and water supply system and plumbing work and upon delivery of the building, the Contractor shall submit the "as-built" drawings of all the plumbing system layouts as actually installed in the building for future reference.

TS-34 Testing

34.1 Materials shall be subjected to such standard tests as may be required to ascertain their fitness, and the complete plumbing system shall be tested by anyone of the following methods.

34.2 The water shall be applied to the plumbing system in it's entirely or in sections. If applied to the entire system, all openings in the piping system shall be tightly closed except the highest opening and the entire system filled with water to the pint of overflow. All dead ends shall be relieved of air during the process whether the test is by section or it entirely. If the system is tested by sections, each opening of section shall be filled with water.

34.3 The air test shall be made by attaching the air compressor or test apparatus to any suitable opening, and closing all other openings of the system, then forcing air into the system until there is a uniform pressure sufficient to balance a column of mercury 0.13 meter in height or 44kg/m. on the entire system. This pressure shall be maintained for ten (10) minutes without any show

of loss in the pressure.

TS-35 Disinfection

The entire water distribution shall be thoroughly, flushed and disinfected with a solution containing not less than fifty (50) part per million (50 ppm) of available chloride. The chlorinating materials shall be either liquid chloride or calcium in the system for a period of sixteen (16) hours, during which all valves and faucets shall be opened and closed several times. After disinfection, the solution shall be flushed from the system with clean water until the residual chlorine content is not greater than 0.2 parts per million.

TS-36 Cleaning and Painting

All exposed metal surfaces shall be rid of grease dirt or other foreign materials. Chrome or nickel-plated piping, fittings and trimmings shall be polished upon completion. All equipment, pipes, valves and fittings shall be cleaned of greased and sludge.

a. Any damages to the building finish or furnishing due to the Contractor's failure to properly clean the piping system shall be repaired by the Contractor at his expense.

b. All exterior surfaces of piping to be installed in or through concrete, tile floors and underground shall be given one coat of acid-resisting paint with a bituminous base.

c. At the completion of all work the fixtures, fittings, accessories and other materials shall be thoroughly cleaned and delivered in a condition to the satisfaction of the Engineer.

TS-37 Maintenance

The Contractor shall maintain and keep the works in good condition in accordance with Specification. During the period of maintenance, the Contractor shall make good all defects which may appear in the pipelines trench, and in the lots in which the pipes are lined.

I. ELECTRICAL WORKS

TS-38 General

38.1 The work include furnishing, delivery and installation of all materials, equipment and labor, necessary for the complete execution of all the Electrical Work as shown on the drawings and as specified herein. All installation shall conform to the requirements of the latest edition of the Philippine Electrical Code (PEC) and the rules and regulations of local and national authorities concerned with the enforcement of the electrical laws and the requirements of the local power company.

38.2 The Contractor shall also provide necessary grounding, if requested by the local electrical cooperatives/power sources in cases of the line to ground connection/ facilities.

TS-39 Materials

39.1 All materials shall be new and of high quality which shall conform to this specification and other applicable standards.

39.2 All electrical materials shall meet the requirements and shall bear inspection label whenever standards have been established. Before any materials are ordered, the Contractor shall submit to the Engineer for the approval a complete list of manufacturer's name, address, descriptive data, trade name of items, etc. which the Contractor proposes to use or install.

a. Wires

All wires shall be copper, soft drawn and annealed, and of ninety eight (98) percent conductivity, they shall be smooth and true and of cylindrical form and shall be within one (1) percent of the actual size called for.

Wires for lighting system shall be thermoplastic installed for 600 Volts unless otherwise noted on the drawings or specified herein.

All wires shall comply with the requirements of the Underwriter's Laboratories, the A.S.T.M. and I.P.C.E.A. as they apply to the particular usage. For lighting system no wire smaller than 2.0 mm sq. shall be used.

b. Plate and receptacles

Type of color of receptacles outlet plates shall be as selected by the Engineer. All switches and receptacles plates shall be of ivory plastic cover or as directed by the Engineer.

c. Panel Board

Lighting panel convenience outlet and other electrical runs, shall be equipped with circuit breakers as indicated in the plans. Branch circuit breaker shall be plug-in type, while main circuit breaker shall be bolt-on type. Circuit breaker shall be enclosed on hinged metal box or cabinet to suit the size and rating to prevent the entrance of water and tampering by unauthorized persons.

d. Junction and Pull Boxes

Junction and pull boxes, of acceptable gauge steel, shall be provided as indicated or as required for facilitating the pulling of wires and cables. Pull boxes in finish places shall be located and installed with the permission and to the satisfaction of the Engineer. Splices and taps in any system shall be made only in junction boxes.

e. Wall Switches

Wall switches shall be rated 5 amperes with voltage rating as required and shall be tumbler operation and the color plating and appearance of wall plate shall be as selected by the Engineer.

f. Electrical Fixtures

All fluorescent shall be equipped with 40 watts fluorescent lamp with HPF ballast or approved equivalent.

g. Raceways

Rigid non-metallic conduit (PVC) shall be used on all installations embedded in concrete and concealed in wood ceilings or walls inside the building only. Rigid non-metallic conduit may be buried directly in earth provided the depth shall not be less than 457 mm (18"). Bends in conduits shall be so made that the conduit won't be injured and that the internal diameter of the conduit will not be

effectively reduce. A complete run of conduit shall not contain more than the equivalent of four quarter bends including those located immediately at the outlet of fitting. Whenever necessary a pull box shall be provided as directed. No conduit shall be used in any system smaller than 15mm (1/2") electrical trade size. All conduits for underground electrical installations shall be rigid steel conduit(RSC) encased in 0.10 x 1.10M concrete.

TS-40 Location of Wiring and Outlet

40.1 The location of outlets shown on diagrammatic wiring plans be considered as approximate and it shall be responsibility of the Contractor, before installation of outlet boxes, to study, verify and obtain precise information from all pertinent drawing, for exact location of all outlets and wiring. If so directed by the Engineer, the Contractor shall make any necessary adjustment of his work to fit conditions for recessed fixtures and for outlets occurring in glazed tile, block, wood paneling or other finish material, in order that all boxes may register flushed with finish. Local switches which are shown near doors as shall be located at the strike side of the doors as finally hung, regardless of swing shown on the drawings as maybe directed by the Engineer.

40.2 All wiring and lighting fixture shall be installed as specified and at location shown on plans.

40.3 Mounting heights of devices shall be detailed as follows if not specified on the drawing or as may be directed by the Engineer.

- a. Light Switches 1.40 m above finish floor
- b. Convenience Outlet 0.30 m above finish floor
- c. Panel Board 1.70 m above finish floor

TS-41 Testing

41.1 The entire installation shall be free from improper grounds and from short circuits. These tests shall be made in the presence of the Engineer. Panel board shall be tested with mains connected to the feeder, branches connected and switches closed, all fixture in place and permanently connected, lamps removed or omitted from the sockets and all wall switches closed. Each individual power feeder shall be tested with the power equipment connected for proper and intended operation. In no case shall the insulation resistance be less than that allowed by the Regulations for Electrical Equipment of Buildings. Failure shall be connected in a manner satisfactory to the Engineer.

41.2 It shall be the responsibility of the Contractor to test all system of the entire electrical installation in the presence of the Engineer, for proper operational condition. This condition shall apply to the power and lighting installation, where sequence operation is required, the Contractor shall test for proper sequence and he shall leave the entire electrical installation in satisfactory working condition.

TS-42 Guarantee

The Contractor shall guarantee that the electrical systems are free from improper grounds and defective materials for a period of one (1) year from date

Section VII. Drawings

[Insert here a list of Drawings. The actual Drawings, including site plans, should be attached to this section, or annexed in a separate folder.]



3D RENDERING OF SLAUGHTERHOUSE MONITOR

PERSPECTIVE VIEW

REPUBLIC OF THE PHILIPPINES
 PROVINCE OF BAMBALON
 MUNICIPALITY OF SANTIAGO

REPUBLIC OF THE PHILIPPINES
 MUNICIPALITY OF SANTIAGO
 OFFICE OF THE MUNICIPAL ENGINEER
 DESIGN & PLANNING

Edgar
 EDGAR DE VERA SAUR
 ENGINEER (REGISTERED)


Edgar
 EDGAR DE VERA SAUR
 MUNICIPAL ENGINEER

Elaine
 ELAINE D. ROSA
 ARCHITECT

PROJECT TITLE/NO. CONSTRUCTION OF MUNICIPAL
 SLAUGHTERHOUSE PHASE III

SHEET NO.





1 SITE DEVELOPMENT PLAN

design of the proposed
 construction
 on 15/11/2018

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
A1	A2	A3	A4	A5	A6	A7	A8	A9	A10	A11	A12	A13	A14	A15	A16	A17	A18	A19	A20	A21	A22	A23	A24	A25	A26	A27	A28	A29	A30	A31	A32	A33	A34	A35	A36	A37	A38	A39	A40	A41	A42	A43	A44	A45	A46	A47	A48	A49	A50	A51	A52	A53	A54	A55	A56	A57	A58	A59	A60	A61	A62	A63	A64	A65	A66	A67	A68	A69	A70	A71	A72	A73	A74	A75	A76	A77	A78	A79	A80	A81	A82	A83	A84	A85	A86	A87	A88	A89	A90	A91	A92	A93	A94	A95	A96	A97	A98	A99	A100



SITE
 MUNICIPAL ENGINEERING
 & SURVEYING
 15/11/2018

**CONSTRUCTION OF MUNICIPAL
 SLAUGHTERHOUSE PHASE III**

[Signature]
 MUNICIPAL ENGINEER

[Signature]
 SENIOR ENGINEER

[Signature]
 MUNICIPAL ENGINEER

**REPUBLIC OF THE PHILIPPINES
 PROVINCE OF SOUTHERN
 LUZON
 MUNICIPALITY OF SANTA RITA**


MUNICIPALITY OF SANTA RITA



PARTITION SCHEDULE

1	1/2" Gypsum Board on 2x4 Studs
2	1/2" Gypsum Board on 2x4 Studs
3	1/2" Gypsum Board on 2x4 Studs
4	1/2" Gypsum Board on 2x4 Studs
5	1/2" Gypsum Board on 2x4 Studs
6	1/2" Gypsum Board on 2x4 Studs
7	1/2" Gypsum Board on 2x4 Studs

1. ALL PARTITIONS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE 2009 INTERNATIONAL BUILDING CODE (IBC) AND THE 2009 INTERNATIONAL RESIDENTIAL CODE (IRC).
 2. ALL PARTITIONS SHALL BE FINISHED WITH A WHITE GYPSUM BOARD ON 2x4 STUDS.
 3. ALL PARTITIONS SHALL BE FINISHED WITH A WHITE GYPSUM BOARD ON 2x4 STUDS.
 4. ALL PARTITIONS SHALL BE FINISHED WITH A WHITE GYPSUM BOARD ON 2x4 STUDS.
 5. ALL PARTITIONS SHALL BE FINISHED WITH A WHITE GYPSUM BOARD ON 2x4 STUDS.
 6. ALL PARTITIONS SHALL BE FINISHED WITH A WHITE GYPSUM BOARD ON 2x4 STUDS.
 7. ALL PARTITIONS SHALL BE FINISHED WITH A WHITE GYPSUM BOARD ON 2x4 STUDS.



GENERAL FLOOR PLAN
 PROPOSED SLAUGHTERING BUILDING
 SHEET NO. 1 OF 1

<p> REPUBLIC OF THE PHILIPPINES PROVINCE OF PANGASINAN MUNICIPALITY OF SANTE </p>	<p> OFFICE OF THE PROBATION OFFICER OFFICE OF THE MUNICIPAL ENGINEER DESIGN & PLANNING </p>	<p> PROPOSER  ENGR. [Name] REGISTERED PROFESSIONAL ENGINEER </p>	<p> DESIGNER  ENGR. [Name] REGISTERED PROFESSIONAL ENGINEER </p>	<p> CLIENT A-2 CONSTRUCTION OF MUNICIPAL SLAUGHTERHOUSE PHASE III </p>
--	--	---	---	---



REPUBLIC OF THE PHILIPPINES
 PROVINCE OF MARIKINA
 MUNICIPAL OFFICE

REPUBLIC OF THE PHILIPPINES
 MUNICIPALITY OF STA. LOUIS
 OFFICE OF THE MUNICIPAL ENGINEER
 BUSINESS & PLANNING


[Signature]
 ENGR. DEAN S. GLEN
 OFFICE OF THE MUNICIPAL ENGINEER

[Signature]
 ENGR. RICHARD M. DELA CRUZ
 OFFICE OF THE MUNICIPAL ENGINEER

[Signature]
 ENGR. JESSIE S. BARRERA
 OFFICE OF THE MUNICIPAL ENGINEER

CONSTRUCTION OF MUNICIPAL
 SLAUGHTERHOUSE PHASE III

A-3



A

C

D

E

F

G

22M

11.5M


11.5M

11.5M

11.5M

11.5M

11.5M



ARCHITECTURAL FINISH SCHEDULE

1	SMOOTH PLASTER	1	PAINT
2	SMOOTH PLASTER	2	PAINT
3	SMOOTH PLASTER	3	PAINT
4	SMOOTH PLASTER	4	PAINT
5	SMOOTH PLASTER	5	PAINT
6	SMOOTH PLASTER	6	PAINT

LEFT SIDE ELEVATION



GOVERNMENT OF PUNJAB
 PROVINCE OF PUNJAB
 MUNICIPALITY OF SARGODHA

OFFICE OF THE MUNICIPAL ENGINEER
 MUNICIPALITY OF SARGODHA

Signature
 ENGINEER IN CHARGE

Signature
 ENGINEER IN CHARGE

Signature
 ENGINEER IN CHARGE

CONSTRUCTION OF MUNICIPAL
 SLAUGHTERHOUSE PHASE III

A-4

A

C


D

E

F

G

1.05 1.30 2.30 1.05



ARCHITECTURAL FINISH SCHEDULE


1	WALLS AND CEILING	PLASTER	PAINT
2	FLOORING	CONCRETE	PAINT
3	ROOFING	CEMENT	PAINT

RIGHT SIDE ELEVATION


	REPUBLIC OF THE PHILIPPINES PROVINCE OF ILOCOS NORTHERN MUNICIPALITY OF SAN JACINTO	REGISTERED PROFESSIONAL ENGINEER CIVIL ENGINEER 	REGISTERED ARCHITECT 	REGISTERED ARCHITECT 	REGISTERED ARCHITECT 	REGISTERED ARCHITECT
--	---	--	--------------------------	--------------------------	--------------------------	--------------------------

CONSTRUCTION OF MUNICIPAL SLAUGHTERHOUSE PHASE III


A-5




PROPOSED SLAUGHTER HOUSE
ROOF PLAN



P-1	FIXED WINDOW	0.90	2.16
P-2	DOOR	0.70	1.80
P-3	WINDOW	0.90	1.80
P-4	WINDOW	0.90	1.30
P-5	WINDOW	0.90	1.30



P-6	WINDOW	0.90	0.90
P-7	WINDOW	0.90	0.90
P-8	WINDOW	0.90	0.90
P-9	WINDOW	0.90	0.90



P-10	WINDOW	0.90	0.90
P-11	WINDOW	0.90	0.90
P-12	WINDOW	0.90	0.90
P-13	WINDOW	0.90	0.90

REPUBLIC OF THE PHILIPPINES
PROVINCE OF RIZAL
MUNICIPALITY OF SANTA

OFFICE OF THE PROGRESSIVE
MUNICIPALITY OF SANTA
OFFICE OF THE MUNICIPAL
BUSINESS & PLANNING

PROJECT NO. 12345

CONSTRUCTION OF MUNICIPAL
SLAUGHTERHOUSE PHASE III

DATE: 12/15/2023

SCALE: 1/4" = 1'-0"

PROJECT NO. 12345

DATE: 12/15/2023

SCALE: 1/4" = 1'-0"

PROJECT NO. 12345

DATE: 12/15/2023

SCALE: 1/4" = 1'-0"

PROJECT NO. 12345

DATE: 12/15/2023

SCALE: 1/4" = 1'-0"

PROJECT NO. 12345

DATE: 12/15/2023

SCALE: 1/4" = 1'-0"


PROJECT NO. 12345

DATE: 12/15/2023

SCALE: 1/4" = 1'-0"



LONGITUDINAL SECTION



REAR ELEVATION

FRONT ELEVATION

ARCHITECTURAL FINISH SCHEDULE


1	CEILING	CONCRETE	PAINT
2	FLOOR	CONCRETE	PAINT
3	WALL	CONCRETE	PAINT
4	DOOR	WOOD	PAINT
5	WINDOW	WOOD	PAINT
6	STAIR	WOOD	PAINT
7	ROOF	CONCRETE	PAINT

 <p>REPUBLIC OF THE PHILIPPINES PROVINCE OF BENGUET MUNICIPALITY OF SAN MATEO</p>	<p>BOYER BLN OF THE PROGRESS MUNICIPALITY OF SAN MATEO OFFICE OF THE MUNICIPAL ENGINEER DESIGN & PLANNING</p>	<p>ARCHITECT</p>  <p>ENGR. JAYSON S. GARCIA REGISTERED ARCHITECT</p>	<p>ENGINEER</p>  <p>ENGR. CARLOS A. MALABON REGISTERED ENGINEER</p>	<p>CONSTRUCTION OF MUNICIPAL SLAUGHTERHOUSE PHASE III</p>	<p>SECTION A-6</p>
	<p>DATE: 08-23-2020</p>	<p>DATE: 08-23-2020</p>	<p>DATE: 08-23-2020</p>	<p>DATE: 08-23-2020</p>	<p>DATE: 08-23-2020</p>

CILING FINISH

1	ACRYLIC FINISH, SANITIZED, LIGHT GREEN, WITH POLYURETHANE GLOSS PAINT
2	ACRYLIC FINISH, SANITIZED, LIGHT GREEN, WITH POLYURETHANE GLOSS PAINT
3	ACRYLIC FINISH, SANITIZED, LIGHT GREEN, WITH POLYURETHANE GLOSS PAINT
4	ACRYLIC FINISH, SANITIZED, LIGHT GREEN, WITH POLYURETHANE GLOSS PAINT
5	ACRYLIC FINISH, SANITIZED, LIGHT GREEN, WITH POLYURETHANE GLOSS PAINT
6	ACRYLIC FINISH, SANITIZED, LIGHT GREEN, WITH POLYURETHANE GLOSS PAINT
7	ACRYLIC FINISH, SANITIZED, LIGHT GREEN, WITH POLYURETHANE GLOSS PAINT

A
B
C
D
E
F
G



REPUBLIC OF THE PHILIPPINES
OFFICE OF THE MUNICIPAL ENGINEER
CITY OF SAN JOSE DEL MONTE
PROVINCE OF BULACAN
ENGINEERING PLAN
2024


	REPUBLIC OF THE PHILIPPINES MUNICIPALITY OF SAN JOSE DEL MONTE OFFICE OF THE MUNICIPAL ENGINEER DESIGN & PLANNING	ENGR. GABRIEL B. BAYBAY LICENSED PROFESSIONAL ENGINEER MECHANICAL	ARCHITECT	CONSTRUCTION OF MUNICIPAL SLAUGHTERHOUSE - PHASE III	SHEET NO. A-8
--	--	---	-----------	---	----------------------

SCHEDULE OF FOOTING

FOOTING CODE	DIMENSIONS (in meters)	D (in meters)	H (in meters)	1-D (in meters)	rein. details	4th Along Y
F-1	1.50 x 1.50	0.35	1.50	1.15	10 - 10mm Ø	10 - 10mm Ø
F-2	1.20 x 1.20	0.35	1.20	0.85	8 - 10mm Ø	8 - 10mm Ø
F-3	1.00 x 1.00	0.35	1.00	0.65	5 - 10mm Ø	5 - 10mm Ø



COLUMN SCHEDULE - BRICK JO FLOOR TO SECOND FLOOR

COLUMN CODE	DIMENSIONS (in meters)	VERTICAL REINFORCEMENT	SET OF TIES
C-1	0.50 x 0.50	2 - 10mm Ø top, 2 - 12mm Ø base	1
C-2	0.25 x 0.25	4 - 10mm Ø top, 4 - 10mm Ø base	1
C-3	0.30 x 0.30	4 - 10mm Ø top, 4 - 10mm Ø base	1



FOOTING/COLUMN DETAIL

WALL FOOTING DETAIL



1 TYPICAL FOOTING/COLUMN DETAIL

REV. 5

REPUBLIC OF THE PHILIPPINES
 PROVINCE OF ROMBLON
 MUNICIPAL OFFICE


OFFICE OF THE MUNICIPAL ENGINEER
 HENK & PLANNING

ENGR. JAYSON A. ALLANOR
 42 LUPAT ST.
 CANTON, ROMBLON

CONSTRUCTION OF MUNICIPAL
 SLAUGHTERHOUSE PHASE III

S-2

A B C D E F F G





PROJECT NO. 61-1087-1R HOUSE
1 CONCRETE BEAM LAYOUT
 DATE: 11/20/13

CONCRETE BEAM LAYOUT

S-3

CONSTRUCTION OF MUNICIPAL SLAUGHTERHOUSE PHASE III



 ENGR. RAYMOND M. MANON
 LICENSED PROFESSIONAL ENGINEER


 ENGR. DESO F. GALIN
 LICENSED PROFESSIONAL ENGINEER

REPUBLIC OF THE PHILIPPINES
 MUNICIPALITY OF STA. FE
 OFFICE OF THE MUNICIPAL ENGINEER
 DESIGN & PLANNING

REPUBLIC OF THE PHILIPPINES
 PROVINCE OF RIZAL
 MUNICIPALITY OF SANTA FE

A B C D E F G




PROJECTED RAFTER HOUSE
1 ROOF BEAM LAY-OUT
 1/4" = 1'-0"


ROOF BEAM LAYOUT	<p>PROJECT TITLE/LOGO</p> <p>S-4</p> <p>CONSTRUCTION OF MUNICIPAL SLAUGHTERHOUSE PHASE III</p>	<p>DESIGNED BY</p> <p><i>[Signature]</i> ENGR. RAYMUNDO M. TORO LICENSED M.E. PHILIPPINES</p>	<p>APPROVED BY</p> <p><i>[Signature]</i> ENGR. RAYMUNDO M. TORO LICENSED M.E. PHILIPPINES</p>	<p>DESIGNED BY</p> <p><i>[Signature]</i> ENGR. DESIGNER GALIN ENGINEERING CONSULTANT</p>	<p>REPUBLIC OF THE PHILIPPINES MUNICIPALITY OF STA. FE OFFICE OF THE MUNICIPAL ENGINEER DESIGN & PLANNING</p>	<p>REPUBLIC OF THE PHILIPPINES PROVINCE OF RIZAL MUNICIPALITY OF SANTA FE</p>
------------------	---	---	---	--	--	---

B E A M S C H E D U L E


MEMBER	MEMBERS
TOP CHORD MEMBER	1 - 2 X 2 X 1/4"
WEB MEMBER	2 - 2 X 2 X 1/4"
RAFTER MEMBER	2 - 2 X 2 X 1/4"



BEAM MARK	BEAM DIMENSION		REBAR (mm Ø)	STEEL REINFORCEMENT						
	b	h		TOP	BOTTOM	MID SPAN	RIGHT	LEFT	WEB BAR	
B-1	250	400	16mmØ	3	2	2	3	2	1	5 T16 R U P S
B-2	200	250	16mmØ	3	2	2	3	2	1	LOCAL REINFORCER @ 175
RA	240	400	16mmØ	3	2	2	3	2	1	LOCAL REINFORCER @ 175



2 TYPICAL ROOF BEAM DETAILS
SCALE: 1:10MMTS



3 TYPICAL BEAM DETAILS
SCALE: 1:10MMTS

ROOF TRUSS AND RAFTER DETAILS

1	2
---	---



REPUBLIC OF THE PHILIPPINES
 PROVINCE OF BAMBANON
 MUNICIPALITY OF SAN JUAN

REPUBLIC OF THE PHILIPPINES
 MUNICIPALITY OF SAN JUAN
 OFFICE OF THE MUNICIPAL ENGINEER
 DESIGN & PLANNING

ENGR. RAYMUNDO M. JAVIER
 MUNICIPAL ENGINEER

[Signature]
 MUNICIPAL ENGINEER

CONSTRUCTION OF MUNICIPAL
 SLAUGHTERHOUSE PHASE III



PROJECT: SLAUGHTERHOUSE
WATER LINE LAYOUT
 DATE: 11-1982

P-2

CONSTRUCTION OF MUNICIPAL
 SLAUGHTERHOUSE PHASE II

[Signature]
 ENGINEER






[Signature]
 ENGR. RAYMOND M. METER
 REGISTERED PROFESSIONAL ENGINEER

[Signature]
 ENGR. DESMOND GAIN
 REGISTERED PROFESSIONAL ENGINEER

REPUBLIC OF THE PHILIPPINES
 MUNICIPALITY OF STA. ELIZABETH
 OFFICE OF THE MUNICIPAL ENGINEER
 DESIGN & PLANNING





REPUBLIC OF THE PHILIPPINES
 PROVINCE OF BAMBALON
 MUNICIPALITY OF SANTIAGO





REVISIONS

NO.	DESCRIPTION	DATE



4 CONDEMNATION PIT
SCALE: 1/4" = 1'-0"

REPUBLIC OF THE PHILIPPINES
PROVINCE OF RIZAL
MUNICIPALITY OF SWATE

REPUBLIC OF THE PHILIPPINES
MUNICIPALITY OF SWATE
OFFICE OF THE MUNICIPAL ENGINEER
DESIGN & PLANNING

PROJECT: CONSTRUCTION OF MUNICIPAL SLAUGHTERHOUSE PHASE III


DESIGNER: ENGR. RAFAEL M. LUCHAN

DATE: 10/10/2023



SCALE: 1/4" = 1'-0"

P-3

FOUNDATION SCHEDULE




MARK	THK (T)	SIZE		REINFORCEMENT		DEPTH OF EXCAVATION
		X	Y	ALONG X	ALONG Y	
F-1	0.35M	1.20 M	1.20 M	8-16mm#	8-16mm#	1.30 METERS




MAIN REINFORCEMENT	STIRRUPS
16MM # 16B	10mm# BARS, STIRRUPS SPACED 5 @ 50mm, 5 @ 100mm, 3 @ 100mm, 3 @ 100mm, REST @ 200mm O.C.

1 2 A B 1 2 A B



1 FLOOR PLAN SCALE 1:100MPS
 5 FOUNDATION PLAN SCALE 1:100MPS
 6 FRAMING PLAN SCALE 1:100MPS



2 ELEVATION SCALE 1:100MPS
 3 ELEVATION SCALE 1:100MPS
 4 ELEVATION SCALE 1:100MPS

REPUBLIC OF THE PHILIPPINES
 PROVINCE OF BANGALON
 MUNICIPALITY OF SANTA FE

REPUBLIC OF THE PHILIPPINES
 MUNICIPALITY OF SANTA FE
 OFFICE OF THE MUNICIPAL ENGINEER
 DESIGN & PLANNING

ENGR. BESSIE F. JEN
 LICENSED PROFESSIONAL ENGINEER

ENGR. ROBERTO M. JEN
 LICENSED PROFESSIONAL ENGINEER

ENGR. B. JEN
 LICENSED PROFESSIONAL ENGINEER

CONSTRUCTION OF MUNICIPAL
 SLAUGHTERHOUSE PHASE III

P-4

GENERAL NOTES AND SPECIFICATIONS

- ALL ELECTRICAL INSTALLATION WORK SHALL BE DONE IN ACCORDANCE WITH THE PROVISIONS OF THE PHILIPPINE ELECTRICAL CODE, THE RULES, REGULATIONS AND THE ORDINANCES OF THE LOCAL GOVERNMENT AND THE LAWS AND ORDINANCES OF THE LOCAL GOVERNMENT.
- ALL ELECTRICAL WORKS SHALL BE SUPERVISED BY A REGISTERED ELECTRICAL ENGINEER (REE) AND SHALL BE APPROVED BY THE LOCAL GOVERNMENT.
- THE TYPE OF POWER SOURCE TO BE SUPPLIED SHALL BE 230VAC, 1Ø, 60 CYCLES.
- ALL ELECTRICAL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROVISIONS OF THE PHILIPPINE ELECTRICAL CODE, THE RULES, REGULATIONS AND THE ORDINANCES OF THE LOCAL GOVERNMENT AND THE LAWS AND ORDINANCES OF THE LOCAL GOVERNMENT.

- CONDUIT SHALL BE AS FOLLOWS:
 - 35mm Ø PVC CONDUIT
 - 40mm Ø PVC CONDUIT
 - 50mm Ø PVC CONDUIT
 - 75mm Ø PVC CONDUIT
- CONDUIT SHALL BE INSTALLED IN ACCORDANCE WITH THE PHILIPPINE ELECTRICAL CODE, THE RULES, REGULATIONS AND THE ORDINANCES OF THE LOCAL GOVERNMENT AND THE LAWS AND ORDINANCES OF THE LOCAL GOVERNMENT.
- CONDUIT SHALL BE INSTALLED IN ACCORDANCE WITH THE PHILIPPINE ELECTRICAL CODE, THE RULES, REGULATIONS AND THE ORDINANCES OF THE LOCAL GOVERNMENT AND THE LAWS AND ORDINANCES OF THE LOCAL GOVERNMENT.

- CONDUIT SHALL BE INSTALLED IN ACCORDANCE WITH THE PHILIPPINE ELECTRICAL CODE, THE RULES, REGULATIONS AND THE ORDINANCES OF THE LOCAL GOVERNMENT AND THE LAWS AND ORDINANCES OF THE LOCAL GOVERNMENT.
- CONDUIT SHALL BE INSTALLED IN ACCORDANCE WITH THE PHILIPPINE ELECTRICAL CODE, THE RULES, REGULATIONS AND THE ORDINANCES OF THE LOCAL GOVERNMENT AND THE LAWS AND ORDINANCES OF THE LOCAL GOVERNMENT.
- CONDUIT SHALL BE INSTALLED IN ACCORDANCE WITH THE PHILIPPINE ELECTRICAL CODE, THE RULES, REGULATIONS AND THE ORDINANCES OF THE LOCAL GOVERNMENT AND THE LAWS AND ORDINANCES OF THE LOCAL GOVERNMENT.

- CONDUIT SHALL BE INSTALLED IN ACCORDANCE WITH THE PHILIPPINE ELECTRICAL CODE, THE RULES, REGULATIONS AND THE ORDINANCES OF THE LOCAL GOVERNMENT AND THE LAWS AND ORDINANCES OF THE LOCAL GOVERNMENT.
- CONDUIT SHALL BE INSTALLED IN ACCORDANCE WITH THE PHILIPPINE ELECTRICAL CODE, THE RULES, REGULATIONS AND THE ORDINANCES OF THE LOCAL GOVERNMENT AND THE LAWS AND ORDINANCES OF THE LOCAL GOVERNMENT.
- CONDUIT SHALL BE INSTALLED IN ACCORDANCE WITH THE PHILIPPINE ELECTRICAL CODE, THE RULES, REGULATIONS AND THE ORDINANCES OF THE LOCAL GOVERNMENT AND THE LAWS AND ORDINANCES OF THE LOCAL GOVERNMENT.


- CONDUIT SHALL BE INSTALLED IN ACCORDANCE WITH THE PHILIPPINE ELECTRICAL CODE, THE RULES, REGULATIONS AND THE ORDINANCES OF THE LOCAL GOVERNMENT AND THE LAWS AND ORDINANCES OF THE LOCAL GOVERNMENT.
- CONDUIT SHALL BE INSTALLED IN ACCORDANCE WITH THE PHILIPPINE ELECTRICAL CODE, THE RULES, REGULATIONS AND THE ORDINANCES OF THE LOCAL GOVERNMENT AND THE LAWS AND ORDINANCES OF THE LOCAL GOVERNMENT.
- CONDUIT SHALL BE INSTALLED IN ACCORDANCE WITH THE PHILIPPINE ELECTRICAL CODE, THE RULES, REGULATIONS AND THE ORDINANCES OF THE LOCAL GOVERNMENT AND THE LAWS AND ORDINANCES OF THE LOCAL GOVERNMENT.

ELECTRICAL LEGENDS



ONE LINE DIAGRAM: POWER

E-4



WIRING SCHEDULE

SINGLE PHASE

- ① 150V 100A 2P 100V 2P 100V 2P
- ② 150V 100A 2P 100V 2P 100V 2P
- ③ 150V 100A 2P 100V 2P 100V 2P
- ④ 150V 100A 2P 100V 2P 100V 2P
- ⑤ 150V 100A 2P 100V 2P 100V 2P
- ⑥ 150V 100A 2P 100V 2P 100V 2P
- ⑦ 150V 100A 2P 100V 2P 100V 2P
- ⑧ 150V 100A 2P 100V 2P 100V 2P

SCHEDULE OF LOADS

Item No.	Load Description	Volts	Amps	Phase	Receptor	Wiring Schedule	Notes
1	10-20watts LED lighting 15' x 10' lights 15'	120	200	2-17	2-17	2-17	20
2	100watts LED lighting 15' x 10' lights 15'	120	200	2-17	2-17	2-17	20
3	3-20watts LED lighting 15' x 10' lights 15'	120	200	2-17	2-17	2-17	20
4	8-20watts LED lighting 15' x 10' lights 15'	120	200	2-17	2-17	2-17	20
5	4-20watts LED lighting 15' x 10' lights 15'	120	200	2-17	2-17	2-17	20
6	150watts LED lighting 15' x 10' lights 15'	120	200	2-17	2-17	2-17	20
7	100watts LED lighting 15' x 10' lights 15'	120	200	2-17	2-17	2-17	20
8	100watts LED lighting 15' x 10' lights 15'	120	200	2-17	2-17	2-17	20
9	100watts LED lighting 15' x 10' lights 15'	120	200	2-17	2-17	2-17	20
10	100watts LED lighting 15' x 10' lights 15'	120	200	2-17	2-17	2-17	20
11	100watts LED lighting 15' x 10' lights 15'	120	200	2-17	2-17	2-17	20
12	100watts LED lighting 15' x 10' lights 15'	120	200	2-17	2-17	2-17	20
13	100watts LED lighting 15' x 10' lights 15'	120	200	2-17	2-17	2-17	20
14	100watts LED lighting 15' x 10' lights 15'	120	200	2-17	2-17	2-17	20

NOTE: 2-20mm sq THHN + 1-10mm sq THHN (minimum is 50mm sq)

REPUBLIC OF THE PHILIPPINES
 MUNICIPALITY OF STA. TERESA
 OFFICE OF THE MUNICIPAL ENGINEER
 DESIGN & PLANNING

REGISTERED ELECTRICAL ENGINEER
 (ELECTRICAL)

REGISTERED ELECTRICAL ENGINEER
 (ELECTRICAL)

REGISTERED ELECTRICAL ENGINEER
 (ELECTRICAL)

REGISTERED ELECTRICAL ENGINEER
 (ELECTRICAL)

REGISTERED ELECTRICAL ENGINEER
 (ELECTRICAL)

REGISTERED ELECTRICAL ENGINEER
 (ELECTRICAL)

REGISTERED ELECTRICAL ENGINEER
 (ELECTRICAL)

REGISTERED ELECTRICAL ENGINEER
 (ELECTRICAL)

Section VIII. Bill of Quantities

Notes on the Bill of Quantities

Objectives

The objectives of the Bill of Quantities are:

- a. to provide sufficient information on the quantities of Works to be performed to enable Bids to be prepared efficiently and accurately; and
- b. when a Contract has been entered into, to provide a priced Bill of Quantities for use in the periodic valuation of Works executed.

In order to attain these objectives, Works should be itemized in the Bill of Quantities in sufficient detail to distinguish between the different classes of Works, or between Works of the same nature carried out in different locations or in other circumstances which may give rise to different considerations of cost. Consistent with these requirements, the layout and content of the Bill of Quantities should be as simple and brief as possible.

Daywork Schedule

A Daywork Schedule should be included only if the probability of unforeseen work, outside the items included in the Bill of Quantities, is high. To facilitate checking by the Entity of the realism of rates quoted by the Bidders, the Daywork Schedule should normally comprise the following:

- a. A list of the various classes of labor, materials, and Constructional Plant for which basic daywork rates or prices are to be inserted by the Bidder, together with a statement of the conditions under which the Contractor will be paid for work executed on a daywork basis.
- b. Nominal quantities for each item of Daywork, to be priced by each Bidder at Daywork rates as Bid. The rate to be entered by the Bidder against each basic Daywork item should include the Contractor's profit, overheads, supervision, and other charges.

Provisional Sums

A general provision for physical contingencies (quantity overruns) may be made by including a provisional sum in the Summary Bill of Quantities. Similarly, a contingency allowance for possible price increases should be provided as a provisional sum in the Summary Bill of Quantities. The inclusion of such provisional sums often facilitates budgetary approval by avoiding the need to request periodic supplementary approvals as the future need arises. Where such provisional sums or contingency allowances are used, the SCC should state the manner in which they will be used, and under whose authority (usually the Procuring Entity's Representative's).

The estimated cost of specialized work to be carried out, or of special goods to be supplied, by other contractors should be indicated in the relevant part of the Bill of Quantities as a particular provisional sum with an appropriate brief description. A separate procurement procedure is normally carried out by the Procuring Entity to select such specialized contractors. To provide an element of competition among the Bidders in respect of any facilities, amenities, attendance, etc., to be provided by the successful Bidder as prime Contractor for the use and convenience of the specialist contractors, each related provisional sum should be followed by an item in the Bill of Quantities inviting the Bidder to quote a sum for such amenities, facilities, attendance, etc.

Signature Box

A signature box shall be added at the bottom of each page of the Bill of Quantities where the authorized representative of the Bidder shall affix his signature. Failure of the authorized representative to sign each and every page of the Bill of Quantities shall be a cause for rejection of his bid.

These Notes for Preparing a Bill of Quantities are intended only as information for the Procuring Entity or the person drafting the Bidding Documents. They should not be included in the final documents.

BILL OF QUANTITIES

Project Name : CONSTRUCTION OF SLAUGHTERHOUSE – PHASE III
 Location : Sitio Lungaog, Poblacion, Santa Fe, Romblon

<i>Item No.</i>	<i>Description</i>	<i>Quantity</i>	<i>Unit</i>	<i>Unit Cost</i>	<i>Total Cost</i>
B.5/B.7 (2)	Community Facility - Project Billboard, Occupational Safety and Health	1	Lot		
1032	Painting Works - Interior/Exterior Wall of Perimeter Fence and Flooring of Slaughterhouse	1	Lot		
1100/1102	Electrical Works - Installation/Erection of Electric Post/fittings and accessories	1	Lot		
1600/1603	Plumbing Works - Drilling, Pipe Layout and Installation/Erection of Water Tank	1	Lot		
1718/1721	Sanitary Works - Sewerage System	1	lot		
I	Equipment - Delivery, Installation and Commissioning of Slaughterhouse Equipment	1	lot		
Total Project Cost				P	

Total Amount in Words: _____

Submitted by:

 Name and Signature of Bidder's Authorized Representative

 Date

Position: _____

Name of Bidder: _____

Section IX. Checklist of Technical and Financial Documents

Notes on the Checklist of Technical and Financial Documents

The prescribed documents in the checklist are mandatory to be submitted in the Bid, but shall be subject to the following:

- a. GPPB Resolution No. 09-2020 on the efficient procurement measures during a State of Calamity or other similar issuances that shall allow the use of alternate documents in lieu of the mandated requirements; or
- b. any subsequent GPPB issuances adjusting the documentary requirements after the effectivity of the adoption of the PBDs.

The BAC shall be checking the submitted documents of each Bidder against this checklist to ascertain if they are all present, using a non-discretionary “pass/fail” criterion pursuant to Section 30 of the 2016 revised IRR of RA No. 9184.

Checklist of Technical and Financial Documents

I. TECHNICAL COMPONENT ENVELOPE

Class "A" Documents

Legal Documents

- (a) Valid PhilGEPS Registration Certificate (Platinum Membership) (all pages) in accordance with Section 8.5.2 of the IRR;

Technical Documents

- (b) Statement of the prospective bidder of all its ongoing government and private contracts, including contracts awarded but not yet started, if any, whether similar or not similar in nature and complexity to the contract to be bid; **and**
- (c) Statement of the bidder's Single Largest Completed Contract (SLCC) similar to the contract to be bid, except under conditions provided under the rules; **and**
- (d) Special PCAB License in case of Joint Ventures **and** registration for the type and cost of the contract to be bid; **and**
- (e) Original copy of Bid Security. If in the form of a Surety Bond, submit also a certification issued by the Insurance Commission **or** original copy of Notarized Bid Securing Declaration; **and**
- (f) Project Requirements, which shall include the following:
- a. Organizational chart for the contract to be bid;
 - b. List of contractor's key personnel (*e.g.*, Project Manager, Project Engineers, Materials Engineers, and Foremen), to be assigned to the contract to be bid, with their complete qualification and experience data;
 - c. List of contractor's major equipment units, which are owned, leased, and/or under purchase agreements, supported by proof of ownership or certification of availability of equipment from the equipment lessor/vendor for the duration of the project, as the case may be; **and**
- (g) Original duly signed Omnibus Sworn Statement (OSS) **and** if applicable, Original Notarized Secretary's Certificate in case of a corporation, partnership, or cooperative; or Original Special Power of Attorney of all members of the joint venture giving full power and authority to its officer to sign the OSS and do acts to represent the Bidder.

Financial Documents

- (h) The prospective bidder's computation of Net Financial Contracting Capacity (NFCC).

Class "B" Documents

- (i) If applicable, duly signed joint venture agreement (JVA) in accordance with RA No. 4566 and its IRR in case the joint venture is already in existence **or** duly notarized statements from all the potential joint venture partners stating that they will enter into and abide by the provisions of the JVA in the instance that the bid is successful.

II. FINANCIAL COMPONENT ENVELOPE

- (j) Original of duly signed and accomplished Financial Bid Form; **and**

Other documentary requirements under RA No. 9184

- (k) Original of duly signed Bid Prices in the Bill of Quantities; **and**
- (l) Duly accomplished Detailed Estimates Form, including a summary sheet indicating the unit prices of construction materials, labor rates, and equipment rentals used in coming up with the Bid; **and**
- (m) Cash Flow by Quarter.

Statement of all ongoing government and private contracts, including contracts awarded but not yet started, if any, whether similar or not similar in nature and complexity to the contract to be bid

Business Name: _____
 Business Address: _____

Name and Location of Contract	Date of Contract	Contract Duration	Owner's Name and Address	Nature of Work	Contractor's Role (Sole Contractor, Subcontractor and Percentage of Participation)		a. Total Contract Value at Award	b. Total Contract Value at Completion	Date of Completion or Estimated Completion Time	% of Accomplishment		Value of Outstanding Works	
					Description	%				Planned	Actual	%	Php
<u>GOVERNMENT:</u>													
<u>PRIVATE:</u>													

* Each item in the statement shall be supported by: Contract Agreement, Notices of Award and/or Notices to Proceed

Submitted by: _____
 (Printed Name & Signature)
 Designation: _____
 Date: _____

Statement of Single Largest Completed Contract which is Similar in Nature
(indicate only one)

Business Name: _____
 Business Address: _____

Name and Location of Contract	Date of Contract	Contract Duration	Owner's Name and Address	Nature of Work	Contractor's Role (Sole Contractor, Subcontractor and Percentage of Participation)		a. Total Contract Value at Award b. Total Contract Value at Completion	Date of Completion or Estimated Completion Time	% of Accomplishment	
					Description	%			Planned	Actual
GOVERNMENT:										
PRIVATE:										

- Note: This statement shall be supported with:**
1. Contract Agreement
 2. Notice of Award and/or Notice to Proceed
 3. Owner's Certificate of Acceptance and/or Contractors Performance Evaluation System (CPES) rating sheet

Bid Securing Declaration Form

[shall be submitted with the Bid if bidder opts to provide this form of bid security]

REPUBLIC OF THE PHILIPPINES)

CITY OF _____) S.S.

BID SECURING DECLARATION

Project Identification No.: *[Insert number]*

To: *[Insert name and address of the Procuring Entity]*

I/We, the undersigned, declare that:

1. I/We understand that, according to your conditions, bids must be supported by a Bid Security, which may be in the form of a Bid Securing Declaration.
2. I/We accept that: (a) I/we will be automatically disqualified from bidding for any procurement contract with any procuring entity for a period of two (2) years upon receipt of your Blacklisting Order; and, (b) I/we will pay the applicable fine provided under Section 6 of the Guidelines on the Use of Bid Securing Declaration, within fifteen (15) days from receipt of the written demand by the procuring entity for the commission of acts resulting to the enforcement of the bid securing declaration under Sections 23.1(b), 34.2, 40.1 and 69.1, except 69.1(f), of the IRR of RA No. 9184; without prejudice to other legal action the government may undertake.
3. I/We understand that this Bid Securing Declaration shall cease to be valid on the following circumstances:
 - a. Upon expiration of the bid validity period, or any extension thereof pursuant to your request;
 - b. I am/we are declared ineligible or post-disqualified upon receipt of your notice to such effect, and (i) I/we failed to timely file a request for reconsideration or (ii) I/we filed a waiver to avail of said right; and
 - c. I am/we are declared the bidder with the Lowest Calculated Responsive Bid, and I/we have furnished the performance security and signed the Contract.

IN WITNESS WHEREOF, I/We have hereunto set my/our hand/s this ____ day of *[month]* *[year]* at *[place of execution]*.


[Insert NAME OF BIDDER OR ITS AUTHORIZED REPRESENTATIVE]

[Insert signatory's legal capacity]

Affiant

[Jurat]

[Format shall be based on the latest Rules on Notarial Practice]



CONTRACTOR'S ORGANIZATIONAL CHART FOR THE CONTRACT

Submit a copy of the Organizational Chart that the Contractor intends to use to execute the Contract if awarded to it. Indicate in the chart the names of the Project Manager, Project Engineer, Materials Engineer, Construction Safety Officer, Foreman, First Aider and other Key Personnel.

Attach the Organizational Chart for the Contract

Name and Signature of Bidder's Representative:

Date:

Position:

Name of Bidder:

**LIST OF CONTRACTOR'S KEY PERSONNEL TO BE ASSIGNED TO THE
CONTRACT, WITH THEIR QUALIFICATION DATA**

[Date of Issuance]

The Chairman

Bids and Awards Committee

Municipality of Santa Fe

Province of Romblon

Dear Sir/Madame:

Supplementing our Organizational Chart for the above-stated Contract, we submit, and certify as true and correct, the following information:

1. We have engaged the services of the following key personnel to perform the duties of the positions indicated in the above-stated Contract if it is awarded to us:

Proposed Position (<i>as applicable</i>)	Name	Years of Experience	
		General Experience	Relevant Experience
Project Manager			
Project Engineer			
Materials Engineer			
Foreman			
Construction Safety Officer			
First Aider			
<i>Others (specify)</i>			

2. We submit the enclosed Curriculum Vitae and Affidavits of Commitment to Work on the Contract of these key personnel.
3. We ensure that the above-mentioned personnel shall employ their best care, skill and ability in performing the duties of their respective position in accordance with the provisions of the Contract, including the Conditions of Contract, Specifications, and Drawings, and that they shall be personally present in the jobsite during the period of their assignment in the Contract.
4. In the event that we choose to replace any of the abovementioned key personnel, we shall submit to you in writing at least fourteen (14) days before making the replacement,

5. We understand that any violation of the above-stated conditions shall be a sufficient ground for us to be disqualified from this Contract and future biddings of the of the LGU - Santa Fe, Romblon.

Very truly yours,

Note: This list must be supported by Curriculum Vitae and Affidavit of Commitments to Work on the Contract of all personnel.

CURRICULUM VITAE

Proposed Position : _____

Name of Firm : _____

Name of Staff : _____

Profession : _____

Date of Birth : _____

Years with Firm/Entity: _____ Nationality: _____

Membership in Professional Societies: _____

Detailed Tasks Assigned: _____

Key Qualifications:

[Give an outline of staff member's experience and training most pertinent to tasks on project. Describe degree of responsibility held by staff member on relevant previous projects and give dates and locations.]

Education:

[Summarize college/university and other specialized education of staff members, giving names of schools, dates attended, and degrees obtained.]

Employment Record:

[Starting with present position, list in reverse order every employment held. List all positions held by staff member since graduation, giving dates, names of employing organizations, titles of positions, held, and locations of projects. Give client reference.]

Certification:

I, the undersigned, certify that to the best of my knowledge and belief, these data correctly describe me, my qualifications, and my experience.

_____ Date: _____

[Signature of staff member over printed name]

**KEY PERSONNEL'S AFFIDAVIT OF COMMITMENT TO WORK
ON THE CONTRACT**

[Date of Issuance]

The Chairman

Bids and Awards Committee

Municipality of Santa Fe

Province of Romblon

Dear Sir/Madame:

1. I, confirm (Name of Professional/Individual) have committed my services for the position of (Key Personnel Position) for the Contract if it is awarded to the Bidder.

2. I, therefore, commit to assume the said position for the Contract once it is awarded to the Bidder, and I shall employ the best care, skill and ability to perform the duties of such position in accordance with the Conditions of Contract, Specifications, Drawings and other provisions of the Contract Agreement. I am aware that I have to stay in the jobsite for the duration of my assignment.

3. I do not allow the use of my name to enable the Bidder to qualify for the Contract without my commitment to assume the said position, since I understand that to do so shall be a sufficient ground for my disqualification from this Contract and future biddings of the Municipal Government of Santa Fe.

4. I submit and certify as true and correct, the following information:

- a. Name : _____
- b. Date of Birth : _____
- c. Nationality : _____
- d. Profession : _____
- e. PRC License No. and Date of Validity: _____
- f. Employment Record and Work Experience Relevant to the Project: (Please fill in the table below; use additional sheet(s) if necessary):

i. Project Name & Location ii. Project Owner's Name & Address iii. Employer's Name & Address iv. Position	i. Project Description ii. Total Project Cost	i. Part of Project Handled ii. Cost of Part	i. Start Date of the Project ii. Completion Date of the Project iii. Total Period of Engagement to the Project
Completed Projects:			
On-going Projects:			

Name and Signature of Professional/Individual Committing to the Contract

Date

SUBSCRIBED AND SWORN to before me this _____ day of _____ at _____, Philippines. Affiant/sis/are personally known to me and was/were identified by me through competent evidence of identity as defined in the 2004 Rules on Notarial Practice (A.M. No. 02-8-13-SC). Affiant/s exhibited to me his/her _____ with his photograph and signature appearing thereon with no. _____.

Witnessed my hand and seal this _____ day of _____.

NAME OF NOTARY PUBLIC

Doc. No. _____
Page No. _____
Book No. _____
Series of. _____

LIST OF EQUIPMENT, OWNED OR LEASED AND/OR UNDER PURCHASE AGREEMENT, PLEDGED TO THE PROPOSED CONTRACT

Business Name: _____

Business Address: _____

Description	Model/Year	Capacity/Performance/Size	Plate No.	Motor No./Body No.	Location	Condition	Proof of Ownership /Lessor/Vendor
A. Owned							
B. Leased							
C. Under Purchase Agreement							

Note: This List must be supported by proof of ownership, lease and/or purchase agreement. For lease and purchase agreement, such proof must include a certification of availability of equipment from the lessor/vendor for the duration of the project.

Submitted by: _____

(Printed Name & Signature of Authorized Representative)

Designation: _____

Date: _____

STATEMENT OF AVAILABILITY OF KEY PERSONNEL AND EQUIPMENT

[Date of Issuance]

The Chairman

Bids and Awards Committee

Municipality of Santa Fe

Province of Romblon

Dear _____ :

In compliance with the requirement of the Municipal Government of Santa Fe, Romblon Bids and Awards Committee for the bidding of the *[Name of Project]* (“the Project”), we certify that *[Name of the Bidder]* has in its employ key personnel, such as ***Project Manager, Project Engineer, Materials Engineer, Foreman and Construction Safety and Health Officer*** who will be engaged for the construction of the said Project.

Further, we likewise certify the availability of equipment that *[Name of the Bidder]* owns, has under lease, and/or has under purchase agreement that may be used for the Project.

Very truly yours,

[Name of Authorized Representative]

[Position]

Omnibus Sworn Statement (Revised)

[shall be submitted with the Bid]

REPUBLIC OF THE PHILIPPINES)
CITY/MUNICIPALITY OF _____) S.S.

AFFIDAVIT

I, [Name of Affiant], of legal age, [Civil Status], [Nationality], and residing at [Address of Affiant], after having been duly sworn in accordance with law, do hereby depose and state that:

1. *[Select one, delete the other:]*

[If a sole proprietorship:] I am the sole proprietor or authorized representative of [Name of Bidder] with office address at [address of Bidder];

[If a partnership, corporation, cooperative, or joint venture:] I am the duly authorized and designated representative of [Name of Bidder] with office address at [address of Bidder];

2. *[Select one, delete the other:]*

[If a sole proprietorship:] As the owner and sole proprietor, or authorized representative of [Name of Bidder], I have full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for [Name of the Project] of the [Name of the Procuring Entity], as shown in the attached duly notarized Special Power of Attorney;

[If a partnership, corporation, cooperative, or joint venture:] I am granted full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for [Name of the Project] of the [Name of the Procuring Entity], as shown in the attached [state title of attached document showing proof of authorization (e.g., duly notarized Secretary's Certificate, Board/Partnership Resolution, or Special Power of Attorney, whichever is applicable)];

3. [Name of Bidder] is not "blacklisted" or barred from bidding by the Government of the Philippines or any of its agencies, offices, corporations, or Local Government Units, foreign government/foreign or international financing institution whose blacklisting rules have been recognized by the Government Procurement Policy Board, by itself or by relation, membership, association, affiliation, or controlling interest with another blacklisted person or entity as defined and provided for in the Uniform Guidelines on Blacklisting;

4. Each of the documents submitted in satisfaction of the bidding requirements is an authentic copy of the original, complete, and all statements and information provided therein are true and correct;

5. [Name of Bidder] is authorizing the Head of the Procuring Entity or its duly authorized representative(s) to verify all the documents submitted;

6. *[Select one, delete the rest:]*

[If a sole proprietorship:] The owner or sole proprietor is not related to the Head of the Procuring Entity, Procurement Agent if engaged, members of the Bids and Awards Committee (BAC), the

Technical Working Group, and the BAC Secretariat, the head of the Project Management Office or the end-user unit, and the project consultants by consanguinity or affinity up to the third civil degree;

[If a partnership or cooperative:] None of the officers and members of *[Name of Bidder]* is related to the Head of the Procuring Entity, Procurement Agent if engaged, members of the Bids and Awards Committee (BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project Management Office or the end-user unit, and the project consultants by consanguinity or affinity up to the third civil degree;

[If a corporation or joint venture:] None of the officers, directors, and controlling stockholders of *[Name of Bidder]* is related to the Head of the Procuring Entity, Procurement Agent if engaged, members of the Bids and Awards Committee (BAC), the Technical Working Group, and the BAC Secretariat, the head of the Project Management Office or the end-user unit, and the project consultants by consanguinity or affinity up to the third civil degree;

7. *[Name of Bidder]* complies with existing labor laws and standards; and

8. *[Name of Bidder]* is aware of and has undertaken the responsibilities as a Bidder in compliance with the Philippine Bidding Documents, which includes:

- a. Carefully examining all of the Bidding Documents;
- b. Acknowledging all conditions, local or otherwise, affecting the implementation of the Contract;
- c. Making an estimate of the facilities available and needed for the contract to be bid, if any; and
- d. Inquiring or securing Supplemental/Bid Bulletin(s) issued for the *[Name of the Project]*.

9. *[Name of Bidder]* did not give or pay directly or indirectly, any commission, amount, fee, or any form of consideration, pecuniary or otherwise, to any person or official, personnel or representative of the government in relation to any procurement project or activity.

10. In case advance payment was made or given, failure to perform or deliver any of the obligations and undertakings in the contract shall be sufficient grounds to constitute criminal liability for Swindling (Estafa) or the commission of fraud with unfaithfulness or abuse of confidence through misappropriating or converting any payment received by a person or entity under an obligation involving the duty to deliver certain goods or services, to the prejudice of the public and the government of the Philippines pursuant to Article 315 of Act No. 3815 s. 1930, as amended, or the Revised Penal Code.

IN WITNESS WHEREOF, I have hereunto set my hand this ___ day of ___, 20__ at _____, Philippines.

[Insert NAME OF BIDDER OR ITS AUTHORIZED REPRESENTATIVE]

[Insert signatory's legal capacity]

Affiant

[Jurat]

[Format shall be based on the latest Rules on Notarial Practice]

FINANCIAL DOCUMENTS FOR ELIGIBILITY CHECK

A. Summary of the Applicant Firm's/Contractor's assets and liabilities on the basis of the attached income tax return and audited financial statement, stamped "RECEIVED" by the Bureau of Internal Revenue or BIR authorized collecting agent, for the immediately preceding year and a certified copy of Schedule of Fixed Assets particularly the list of construction equipment.

		Year 20 ____
1	Total Assets	
2	Current Assets	
3	Total Liabilities	
4	Current Liabilities	
5	Total Net Worth (1-3)	
6	Current Net Worth or Net Working Capital (2-4)	

B. The Net Financial Contracting Capacity (NFCC) based on the above data is computed as follows:

NFCC = [(Current Assets minus Current Liabilities) (15)] minus the value of all outstanding or uncompleted portions of the projects under ongoing contracts, including awarded contracts yet to be started, coinciding with the contract to be bid.

NFCC = P _____

NFCC must be at least equal to the ABC

The value of bidder's current assets and current liabilities shall be based on the latest Audited Financial Statement submitted to the BIR.

Herewith attached are certified true copies of the income tax return and audited financial statement: stamped "RECEIVED" by the BIR or BIR authorized collecting agent for the immediately preceding year.

Submitted by:

Name of Firm/Contractor

Signature of Authorized Representative

Date: _____

NOTE:

1. If Partnership or Joint Venture, each Partner or Member Firm of Joint Venture shall submit the above requirements.

Bid Form for the Procurement of Infrastructure Projects

[shall be submitted with the Bid]

BID FORM

Date : _____

Project Identification No. : _____

To: *[name and address of Procuring Entity]*

Having examined the Philippine Bidding Documents (PBDs) including the Supplemental or Bid Bulletin Numbers *[insert numbers]*, the receipt of which is hereby duly acknowledged, we, the undersigned, declare that:

- a. We have no reservation to the PBDs, including the Supplemental or Bid Bulletins, for the Procurement Project: *[insert name of contract]*;
- b. We offer to execute the Works for this Contract in accordance with the PBDs;
- c. The total price of our Bid in words and figures, excluding any discounts offered below is: *[insert information]*;
- d. The discounts offered and the methodology for their application are: *[insert information]*;
- e. The total bid price includes the cost of all taxes, such as, but not limited to: *[specify the applicable taxes, e.g. (i) value added tax (VAT), (ii) income tax, (iii) local taxes, and (iv) other fiscal levies and duties]*, which are itemized herein and reflected in the detailed estimates,
- f. Our Bid shall be valid within the a period stated in the PBDs, and it shall remain binding upon us at any time before the expiration of that period;
- g. If our Bid is accepted, we commit to obtain a Performance Security in the amount of *[insert percentage amount]* percent of the Contract Price for the due performance of the Contract, or a Performance Securing Declaration in lieu of the the allowable forms of Performance Security, subject to the terms and conditions of issued GPPB guidelines¹ for this purpose;
- h. We are not participating, as Bidders, in more than one Bid in this bidding process, other than alternative offers in accordance with the Bidding Documents;

¹ currently based on GPPB Resolution No. 09-2020

- i. We understand that this Bid, together with your written acceptance thereof included in your notification of award, shall constitute a binding contract between us, until a formal Contract is prepared and executed; and
- j. We understand that you are not bound to accept the Lowest Calculated Bid or any other Bid that you may receive.
- k. We likewise certify/confirm that the undersigned, is the duly authorized representative of the bidder, and granted full power and authority to do, execute and perform any and all acts necessary to participate, submit the bid, and to sign and execute the ensuing contract for the [Name of Project] of the [Name of the Procuring Entity].
- l. We acknowledge that failure to sign each and every page of this Bid Form, including the Bill of Quantities, shall be a ground for the rejection of our bid.

Name: _____

Legal Capacity: _____

Signature: _____

Duly authorized to sign the Bid for and behalf of: _____

Date: _____

DETAILED ESTIMATES FORM

Project : **CONSTRUCTION OF SLAUGHTERHOUSE – PHASE III**
 Location : Barangay Guinbirayan, Santa Fe, Romblon
 Owner : Municipality of Santa Fe, Romblon
 Date :
 Bidder :

Item of Work : COMMUNICATION FACILITY
 Item Number : B.5/B.7 (2)
 Work Description : Project Billboard, Occupational Safety and Health
 Unit of Measurement : 1 Lot

Description		Quantity	Unit	Unit Cost	Amount
A.	Materials				
	Sub-Total for A				P
Designation		No. of Person	No. of Days	Daily Rate	Amount
B.	Labor				
	Sub-Total for B				P
Description		Quantity	No. of Days	Rate	Amount
C.	Equipment				
	Sub-Total for C				P
D.	Direct Cost (A+B+C)				
E.	Overhead, Contingencies and Miscellaneous (OCM)				
F.	Contractor's Profit (CP)				
G.	Value Added Tax (VAT)				
H.	Total Cost				
I.	Unit Cost				

Item of Work : Painting Works
 Item Number : 1032
 Work Description : Interior/Exterior Wall of Perimeter Fence and Flooring of Slaughterhouse
 Unit of Measurement : 1 Lot

Description		Quantity	Unit	Unit Cost	Amount
A.	Materials				
	Sub-Total for A				P
Designation		No. of Person	No. of Days	Daily Rate	Amount
B.	Labor				
	Sub-Total for B				P
Description		Quantity	No. of Days	Rate	Amount
C.	Equipment				
	Sub-Total for C				P
D.	Direct Cost (A+B+C)				
E.	Overhead, Contingencies and Miscellaneous (OCM)				
F.	Contractor's Profit (CP)				
G.	Value Added Tax (VAT)				
H.	Total Cost				
I.	Unit Cost				

Item of Work : Electrical Works
 Item Number : 1100/1102
 Work Description : Installation/Erection of Electric Post, fittings and accessories
 Unit of Measurement : 1 Lot

Description		Quantity	Unit	Unit Cost	Amount
A.	Materials				
	Sub-Total for A				P
Designation		No. of Person	No. of Days	Daily Rate	Amount
B.	Labor				
	Sub-Total for B				P
Description		Quantity	No. of Days	Rate	Amount
C.	Equipment				
	Sub-Total for C				P
D.	Direct Cost (A+B+C)				
E.	Overhead, Contingencies and Miscellaneous (OCM)				
F.	Contractor's Profit (CP)				
G.	Value Added Tax (VAT)				
H.	Total Cost				
I.	Unit Cost				

Item of Work : Plumbing Works
 Item Number : 1600/1603
 Work Description : Drilling, Pipe Laying and Installation of Water Tank
 Unit of Measurement : 1 Lot

	Description	Quantity	Unit	Unit Cost	Amount
A.	Materials				
	Sub-Total for A				P
	Designation	No. of Person	No. of Days	Daily Rate	Amount
B.	Labor				
	Sub-Total for B				P
	Description	Quantity	Days	Rate	Amount
C.	Equipment				
	Sub-Total for C				P
D.	Direct Cost (A+B+C)				
E.	Overhead, Contingencies and Miscellaneous (OCM)				
F.	Contractor's Profit (CP)				
G.	Value Added Tax (VAT)				
H.	Total Cost				
I.	Unit Cost				

Item of Work : Sanitary Works
 Item Number : 1718/1721
 Work Description : Sewerage System
 Unit of Measurement : 1 Lot

Description		Quantity	Unit	Unit Cost	Amount
A.	Materials				
	a.				
	b.				
	c.				
	Sub-Total for A				P
Designation		No. of Person	No. of Days	Daily Rate	Amount
B.	Labor				
	Sub-Total for B				P
Description		Quantity	No. of Days	Rate	Amount
C.	Equipment				
	Sub-Total for C				P
D.	Direct Cost (A+B+C)				
E.	Overhead, Contingencies and Miscellaneous (OCM)				
F.	Contractor's Profit (CP)				
G.	Value Added Tax (VAT)				
H.	Total Cost				
I.	Unit Cost				

Item of Work : EQUIPMENT
 Item Number : 1
 Work Description : Delivery, Installation and Commissioning of Slaughterhouse
 Unit of Measurement : 1 Lot

Description		Quantity	Unit	Unit Cost	Amount
A.					
	1. HOG RESTRAINER	1	set		
	- V-shape type chamber, made of 3mm Thk s/s plate, full welded construction of grade 304 with hand lever unloader, vertical type entrance gate; dim: 1800mm L x 600mm W x 900mm H				
	2. KNOCKING PEN DOOR WITH ENTRANCE GATE	1	set		
	- Made of 150mm channel bar frame and 3mm thk stainless steel plate revolving door double wall and reinforced with angular steel; Revolving door is mounted on self align bearing with manual lock/unlock hand latch; includes vertical entrance gate, made of 3mm thk ms plate with steel angle frame and counterweight; includes concrete and masonry works				
	3. CARCASS SPREADER MECHANICAL	1	set		
	- Auger type with 90mm maximum stroke; driven by .3kw (0.5hp) tefc motor, 220V ac 1 phase, 60 hz; includes motor control and limit switches as accessories				
	4. ELECTRIC HOIST	1	set		
	- 1500 kgs, capacity (minimum) Chain type hoist; includes pendant type push button switch up and down; hoist is "kito" Japan Made, 220V ac 3 phase, 60 hz or its equivalent				
Sub-Total for A					
B.	Vat				
C.	Freight				
D.	Total Cost				

Grand Total : P _____
 Total Amount in Words : _____

SUMMARY OF BID PRICES

Project Name : CONSTRUCTION OF SLAUGHTERHOUSE – PHASE III
Location : Sitio Lungaog, Poblacion, Santa Fe, Romblon

<i>Item No.</i>	<i>Description</i>	<i>Total Cost</i>
B.5/B.7 (2)	Community Facility	
1032	Painting Works	
1100/1102	Electrical Works	
1600/1603	Plumbing Works	
1718/1721	Sanitary Work	
I	Equipment	
	Total Project Cost	

Total Amount in Words: _____

Submitted by:

Name and Signature of Bidder's Authorized Representative

Date

Position: _____

CASH FLOW BY QUARTER

Project Name : CONSTRUCTION OF SLAUGHTERHOUSE – PHASE III
 Location : Sitio Lungaog, Poblacion, Santa Fe

PARTICULAR	TOTAL	YEAR			
		1 st Quarter	2 nd Quarter	3 rd Quarter	4 th Quarter
Accomplishment, in %	100%				
Cash Flow, in Php					
Cumulative Accomplishment, in %	100%				
Cumulative Cash Flow, in Php					

Submitted by:

Name and Signature of Bidder's Representative:

Position:

Name of Bidder:

Date : _____

